

District Road Works

VOLUME

3

Implementation and Monitoring Manuals

Manual B:

Preparation of Quartely Progress Reports



Ministry of Works, Housing and Communications

JULY 2001

ACKNOWLEDGEMENTS

These manuals have been prepared by the Ministry of Works, Housing and Communications, Uganda.

The aim of the manuals is to complement the Ministry's effort in providing guidance and building capacity of Local Governments to enable them handle their mandated roles in planning and management of the road sector development.

This manual is part of a set titled District Road Works. The set consists of 5 Volumes, each volume comprising a series of manuals covering varying aspects under the following headings:

Volume 1 Planning Manuals

Volume 2 Contract Management Manuals

Volume 3 Implementation and Monitoring Manuals

Volume 4 Technical Manuals

Volume 5 District Administrative and Operational Guidelines

The Manuals describe in detail the organization and techniques for planning, implementation and administration of a district road network. The manuals support Government strategies on sustainable maintenance of district roads; they encourage community participation, promote use of labour based methods and gender balance, ensure protection of the environment, foster work place safety and health in implementation of road works by adopting appropriate contracting practices and support the local construction industry.

They are primarily aimed at Road Engineers, Planners and Managers involved in the planning and management of district road works.

In line with the topics covered in these manuals, related training modules have been designed and are incorporated in the curriculum of the Mount Elgon Labour Based Training Centre.

The manuals are the property of the Ministry of Works, Housing and Communications, but copying and local distribution is not restricted.

We wish to acknowledge the efforts of COWI Consulting Engineers and Planners AS who assisted in the compilation of the Drafts and the invaluable support of the Danish International Development Agency for the financial assistance extended to the Ministry in preparing the manuals.

L.Lutaaya
Engineer in Chief / DE

Volume 3 Manual B

Quarterly Progress Report

Table of Contents

Section B1: General Information

Section B2: Overview of Quaterly Progress Report (QPR)

Section B3: Detailed Instructions for Preparation of the QPR

Annex 1 : Standard Forms including Forms B1, B2, B3 and B4

Annex 2 : Standard Covering Letter Format

Annex 3 : Worked Example

Annex 4 : Users Manual - Quarterly Progress Reporting System (QPRS)

Section B1 General Information

Section B2: Overview of Quaterly Progress Report (QPR)

Section B3: Detailed Instructions for Preparation of the QPR

Annex 1 : Standard Forms including Forms B1, B2, B3 and B4

Annex 2 : Standard Covering Letter Format

Annex 3 : Worked Example

Annex 4 : Users Manual - Quarterly Progress Reporting System (QPRS)

Section B1General Information

General Information	 Page	1-1

GENERAL INFORMATION

This Manual, read together with the following documents;

- PAF General Guidelines for the Planning and Operation of Conditional Grants issued by the Ministry of Finance Planning and Economic Development (MFPED), (Reference I)
- Sector Specific Guidelines for the Planning and Operation of District Road Maintenance & Rehabilitation Programmes issued by the MoWHC-DUR Desk, (Reference II)
- Annual District Road Work Plan (ADRWP), District Road Works Volume 1, Manual D.

provide guidelines for the preparation of the Quarterly Progress Report (QPR) for the following operations -

- Routine Maintenance of District Roads
- Periodic Maintenance of District Roads
- Rehabilitation of District Roads
- Spot Repairs of District Roads and their drainage structures

The PAF General Guidelines clearly states that.... for each Conditional Grant, Local Governments will be required to report every quarter on progress, specifying actual activities carried out, and expenditures on those activities and to submit quarterly request for funds in the form of quarterly work plans.

The PAF General Guidelines go on to say that for each quarter, Local Governments will have to prepare and submit the QPR comprising three essential (3) documents for each Grant including;

- Quarterly Progress Report
- Cumulative Progress Report
- Quarterly Budget Request

and failure to provide this information correctly and in a timely manner may result in the interruption of further fund releases during the current financial year (FY).

The basic reference for the QPR is the ADRWP which provides a description of all the works/operations planned to be undertaken on the district road network during the FY together with the timing of works implementation, their estimated costs including support or operational expenditures, sources of funding, and works implementation and associated expenditure schedules and budget summary; refer Annual District Road Work Plan (ADRWP), District Road Works, **Volume 1, Manual D**.

The ADRWP and QPR documentation, when used together, act as a management information system (MIS) enabling rational planning, programming, implementation and reporting of district road works/operations. The formats used for both the ADRWP and QPR are similar and much of the information can be simply transferred between the two documents. Further, the QPR has been designed to act as a continuous/rolling report and plan allowing for:

Section B1 District Road Manuals

- Reporting on progress during the quarter under report
- Reporting on cumulative progress to date during the FY under report
- Readjusting the work plan to include those activities planned, but not completed, to be brought forward into subsequent quarters and included in future budget requests

The PAF General Guidelines clearly state that the timing for submission of the QPR for each quarter of the FY is the last working day of the first month following the close of the quarter.

The QPR, once prepared by the District Local Government Engineer (DLGE) and prior to transmission to the MoWHC-DUR Desk and copied to the Director Budget, MFPED, shall be approved and signed by the DLGE, the DLG Secretary of Works and the DLG Chief Administrative Office (CAO).

In all cases, the QPR shall be submitted under a covering letter signed by both the CAO and the Department Head responsible for administration of the Grant; in the case of PAF Grants for district road works, this shall be the District Local Government Engineer (DLGE).

Copies of the QPR shall also be provided to the following individuals in the concerned DLG;

- a) DLG Engineer, District
- b) LCV Chairman, District
- c) Sec. of Works, District
- d) Chairperson of the District Public Accounts Committee, District
- e) Chief Internal Auditor, District
- f) RDC, District
- g) Director Budget, MFPED, Kampala
- h) Donor Representative (s) in all cases where donor funds are provided

It is important to note from the outset that the MIS, comprising both the ADRWP and subsequent QPRs, provides a system allowing for continuous updating on a day-to-day basis.

In other words, every time a financial transaction, contract variation, etc., is made, it should be immediately recorded thereby allowing for a rapid compilation/completion of the QPR including updating of the work plan at the end of each and every quarter.

Finally, the MIS provides a system that is continuous/rolling, not only from month to month and quarter to quarter for a specific FY, but also from FY to FY.

Section B1: General Information

Section B2 Overview of Quarterly Progress Report (QPR)

Section B3: Detailed Instructions for Preparation of the QPR

Annex 1 : Standard Forms including Forms B1, B2, B3 and B4

Annex 2 : Standard Covering Letter Format

Annex 3 : Worked Example

Annex 4 : Users Manual - Quarterly Progress Reporting System (QPRS)

Section B2 Overview of Quarterly Progress Report (QPR)

Overview of Quarterly Progress Report (QPR)	Page	2-1
Sources of Funding for Performed & Planned Works	Page	2-1
Expenditure Schedule	Page	2-2
Works Implementation Schedule.	Page	2-2
Summary of Actual Expenditure / Fund Request	Page	2-3
Contract Tracking Format.	Page	2-4
Standard Covering Letter Format	Page	2-4

OVERVIEW OF QUARTERLY PROGRESS REPORT (QPR)

When preparing the QPR, a number of standard formats shall be adopted to ensure that all essential and relevant information is included.

These standard formats include the following -


- Form B1; QPR Expenditure Schedule
- Form B2; QPR Works Implementation Schedule
- Form B3; QPR Summary of Actual Expenditure / Fund Request
- Form B4; QPR Contract Tracking Format
- Standard QPR Covering Letter Format

To assist the DLGE and other district staff with preparation of the QPR, the above standard formats are included in **Annexes 1** and **2** to this Manual and are further described below.

A worked example of a typical QPR is also provided as **Annex 3** to this Manual.

Sources of Funding for Performed & Planned Works

Routine and periodic maintenance, rehabilitation and spot repair works/operations on district roads are funded from a variety of sources including PAF Grants I, II and III, various donors, district development funds, special purpose grants, local revenue and so on.



In most cases, funding sources have pre-conditions attached and may only be used for clearly defined or dedicated purpose(s); these are generally referred to as tied funding sources.

The most common examples of tied funding sources include -

- PAF Grant I dedicated to the implementation of Routine Maintenance operations using labourbased methods
- PAF Grant II dedicated to the implementation of Periodic Maintenance operations using, where feasible, labour-based methods
- PAF Grant III dedicated to the implementation of Rehabilitation operations including Spot Repairs using, where possible, trained local contractors and labour-based methods
- Donor funds with pre-conditions as what works/operations will/will not be funded
- Special purpose grants dedicated to specific works/operations
- Other tied funds

Untied funding sources, inter alia, include district development funds and income generated by the district through general revenue collection.

During preparation of the QPR, it is essential to identify the source/sources of funds that have been / are to be used for implementation of each of the works/operations

PAF Grants I, II and III, funds are dedicated to routine maintenance, periodic maintenance and rehabilitation works respectively and no alternative use of these Grants is permitted.

There will be cases where works/operations are financed from a number of funding sources.


Section B2 District Road Manuals

For example, when undertaking rehabilitation and spot repair works/operations, there may be an opportunity to use both PAF III Grant funds for the rehabilitation works on a road, and donor funds for construction/repair of the drainage structures along the same road.

The clear distinction as to the origin or source of funds for each works/operation is, therefore, of paramount importance to ensure the proper management and administration of the works and for accurate reporting.

EXPENDITURE SCHEDULE

When preparing the Expenditure Schedule of the QPR, the DLGE needs to take account of the following -



- The total scope of all priority works/operations planned during the quarter under report
- The total scope of all priority works/operations actually performed during the quarter under report
- The total funds spent during the quarter under report including their sources
- The total funds available for the remaining quarters of the FY including their sources
- The timing for subsequent works/operations implementation including those not completed during the quarter under report, refer **Section 3** below
- Funding needs for implementation of the works/operations planned in subsequent quarters
- Funding needs for the procurement process and supervision of the works/operations (operational expenses) planned in subsequent quarters


Consideration of the matters raised in **Section 3** below allows realistic timings for implementation of the planned works/operations (including those not completed during the quarter under report) and, therefore, realistic estimates of the cash flow needs throughout the remaining quarters of the FY necessary to meet the planned implementation targets as set out in the ADRWP.

In other words, the Expenditure Schedule (Form B1) provides three very important functions;

- A detailed account of actual expenditures during the quarter under report
- An historical overview of all actual expenditures to date
- The facility to readjust the planned cash flows to provide for future implementation of works/operations including those not completed during the quarter under report

WORKS IMPLEMENTATION SCHEDULE

When preparing the Works Implementation Schedule of the QPR, the DLGE needs to take account of the following -



- The total scope of all priority works/operations planned during the quarter under report
- The total scope of all priority works/operations actually performed during the quarter under report
- The timing for subsequent works/operations implementation including those works not completed during the quarter under report
- Funding needs for implementation of the works/operations planned in subsequent quarters
- Funding needs for the procurement process and supervision of the works / operations (operational expenses) planned in subsequent quarters

Consideration of realistic timings for implementation of the planned works/operations (including those not completed during the quarter under report), and the availability of funding from all sources, allows for a

rational readjustment of the Works Implementation Schedule for the remaining quarters of the FY necessary to meet the planned implementation targets as set out in the ADRWP.

- a) A detailed account of actual works/operations performed during the quarter under report
- b) An historical overview of all actual works/operations performed to date
- c) The facility to readjust the planned timing of works/operations to provide for their future implementation including those not completed during the quarter under report

In other words, the Works Implementation Schedule (Form B2) provides three very important functions;

The Expenditure Schedule (Form B1) and the Works Implementation Schedule (Form B2) together comprise the base line data for the QPR detailing what works/operations have been and are to be implemented, at what cost and when.

It is important, therefore, that these two forms are prepared together and updated together on a regular basis.

SUMMARY OF ACTUAL EXPENDITURE / FUND REQUEST

The Summary of Actual Expenditure / Fund Request provides seven important pieces of information -



- Identification of all actual expenditures by funding source, for the quarter under report
- Identification of all actual expenditures for each individual works/operation for the quarter under report
- An historical overview of all actual expenditures to date by source and for each individual works/operation together with their percentage achievements
- Estimates of the total funding requirements from each funding source for each of the individual works/operations planned for the next quarter
- Estimates of the total funding needs for meeting operational expenses associated with implementation of the works/operations for the next quarter
- Identification of fund balances available at the end of the quarter under report
- Determination of the Total Fund Request for the next quarter for each works/operation and from each funding source.

The importance of this Summary of Actual Expenditure / Fund Request cannot be ignored as it allows those agencies responsible for the release of funds to be aware of;

- The total amounts spent in the quarter under report and to date
- The total amounts required for each of the planned activities in the subsequent quarter
- The total amounts required from each funding source

This information is of particular importance to both the MoWHC-DUR Desk and the MFPED when undertaking quarterly releases of PAF Grant funds.

Finally, the Summary of Actual Expenditure / Fund Request is a tool enabling the DLGE to properly monitor and report on expenditures (and physical progress) not only for each planned activity, but also from each funding source.

Section B2 District Road Manuals

CONTRACT TRACKING FORMAT

The Contract Tracking Format provides a tool for the DLGE to record all transactions related to the implementation of all district road works/operations funded from all sources including PAF Grants.



The form provides for these transactions to be recorded immediately they occur, thereby ensuring that all relevant information is readily available and up-to-date for inclusion in the QPRs.


The form provides vital information regarding the progress of each and every work/operation, whether undertaken under a formal contract or by Force Account.

It allows the day-to-day tracking of performance for each and every work/operation in terms of time worked and physical and financial progress.

This form will be used as the basis for monitoring of district road works/operations by district staff, the MoWHC and other concerned parties.

STANDARD COVERING LETTER FORMAT

The standard covering letter shall, together with its attachments (**Forms B1**, **B2**, **B3** and **B4** above), be the QPR document that provides information required by the Agency responsible for recommending further releases of PAF Grant funds to the district; in the case of district roads, the MoWHC-DUR Desk.



The standard covering letter is a tool enabling the DLGE to provide all essential data necessary for the MoWHC-DUR Desk to report in a comprehensive and timely manner to the MFPED.

The standard covering letter includes three Tables for the entry of summarised data extracted from **Forms B1**, **B2** and **B3**. These three Tables include;

- Table A Summary of Quarterly Progress Report PAF
- Table B Cumulative Summary of Quarterly Progress Report(s) PAF
- Table C Quarterly Budget Request All Funding Sources including PAF

In addition to these three Tables, provision is made in the standard covering letter to list <u>all</u> those district roads on which works/operations were performed during the quarter under report.

Finally, the standard covering letter provides a check-list of all attachments that shall accompany and comprise the whole of what is referred hereto as the QPR.

It cannot be too strongly stressed that all data required for inclusion in the three summary Tables and the list of roads be included and accurately so. Failure to do so may result in the delayed release of PAF Grants.

Detailed instructions for preparation of the QPR are provided in **Section B3** below.

Section B1: General Information

Section B2: Overview of Quaterly Progress Report (QPR)

Section B3 Detailed Instructions for Preparation of the QPR

Annex 1 : Standard Forms including Forms B1, B2, B3 and B4

Annex 2 : Standard Covering Letter Format

Annex 3 : Worked Example

Annex 4 : Users Manual - Quarterly Progress Reporting System (QPRS)

Section B3 Detailed Instructions for Preparation of the QPR

Detailed I	Instructions f	or Preparation	of the QPR	Page	1-1
Detailed		oi i icpaiation		I ago	

DETAILED INSTRUCTIONS FOR PREPARATION OF THE QPR

Before detailing the procedure for preparation of the QPR it is important to fully understand the relationship between the planning process (ADRICS/RAMPS/LGBFP/ADRWP) and the reporting on progress of actual implementation of works/operations as summarised in the QPR.

The ADRWP details those works/operations together with their timing and estimated costs that comprise the annual work plan for the forthcoming FY.

The QPR reports on actual performance, compared to the ADRWP, during the four quarters of the FY.

Here lies the problem!

In the <u>first</u> quarter, the QPR reports progress compared to those specific works/operations and expenditures planned for implementation in the <u>first</u> quarter of the FY and detailed in the ADRWP. This is logical and the way it should be.

However, in the second and subsequent quarters, the QPR has been, at the end of the first, second and third quarters, used to readjust the work plan to accommodate those works/operations not undertaken during the quarter(s) under report; in accordance with the requirements of the PAF General and Sector Specific Guidelines, References I and II.

Therefore, by the end of the first quarter, the ADRWP is out of date!

To continue, in the second, third and fourth quarters, comparing actual works/operations undertaken and their respective expenditures with those planned in the ADRWP is like comparing apples with oranges!

In order to compare apples with apples it is necessary to understand the following.

The work plans for the second, third and fourth quarters are the adjusted timetables for implementation of works/operations and their associated expenditures included in **Forms B1** (Expenditure Schedule) and **B2** (Works Implementation Schedule) of the QPR.

In other words, the work plan for the second quarter is <u>not</u> that shown in the ADRWP, but is that shown in the adjusted figures for the second quarter as detailed in the first quarter's QPR.

The work plan for the third quarter is, again, <u>not</u> that shown in the ADRWP, but is that shown in the adjusted figures for the third quarter as detailed in the second quarter's QPR.

And, finally, the work plan for the fourth quarter is <u>not</u> that shown in the ADRWP, but is that shown in the adjusted figures for the fourth quarter as detailed in the third quarter's QPR.

It is only when preparing the fourth (end of FY) QPR, that reference is again made to the ADRWP in order to <u>compare the actual</u> annual achievement, in terms of total works/operations implementation and total expenditures, <u>with that planned</u> in the ADRWP for the FY.

Finally, those works/operations not undertaken during the current FY are then included in the next FY and the entire process continues as any planning/programming/implementation/reporting system (MIS) should.

What now follows is a step-by-step procedure for preparation of the QPR, comprising **Forms B1**, **B2**, **B3** and **B4** (Annex 1), and the Standard Covering Letter Format (Annex 2).

Section B3 District Road Manuals

STEP 1

It is strongly recommended to complete together and at the same time, Form B1 (Expenditure Schedule) and Form B2 (Works Implementation Schedule).

Form B1 - Planned Expenditure this Quarter and to Date (Ush 000), Columns (a) to (k)

Enter the name of the District, the number of the quarter under report and the FY.

- Column (a) *District Priority Ranking* resulting from the RAMPS; enter the list of roads in their order of priority, commencing with priority number one.
- Column (b) *District Road Link Number*, enter the road numbers in accordance with the MoWHC-DUR Desk's official list.
- Column (c) *Total Road Length* in kilometres (km); enter those road lengths as determined during ADRICS.
- Column (d) *Road Section Length* in km; enter the actual road section lengths on which specific works/ operations are planned to be undertaken.

These four columns shall contain exactly the same information and in its order of presentation as in the ADRWP.

- Columns (e), (f), (g), (h) and (i) Routine Maintenance (RM), Periodic Maintenance (PM), Rehabilitation (RH), Road Bottlenecks (SR), and Structural Bottleneck (ST); enter the planned expenditures for each of the works/operations planned for implementation in the quarter under report.
 - 1. For the first QPR of the FY, Columns (e), (f), (g), (h) and (i) will use the planning data for the first quarter found in Columns (j), (k) and (l) of Form D1 of the ADRWP.
 - 2. For the second QPR of the FY, Columns (e), (f), (g), (h) and (i) will use the adjusted planning data from Columns (o), (p) and (q) found in Form B1 of the first quarter QPR.
 - 3. For the third QPR of the FY, Columns (e), (f), (g), (h) and (i) will use the adjusted planning data from Columns (r), (s) and (t) found in Form B1 of the second quarter OPR.
 - 4. For the fourth QPR of the FY, Columns (e), (f), (g), (h) and (i) will use the adjusted planning data from Columns (u), (v) and (w) found in Form B1 of the third quarter QPR.
 - 5. When preparing the fourth (end of FY) QPR, reference is also made to the ADRWP in order to <u>compare the actual</u> annual achievement, in terms of total works/operations implementation and total expenditures, <u>with that planned</u> in the ADRWP for the FY.
- Column (j) *Total Planned Expenditure this Quarter*, enter the total planned expenditures for each of the works/operations planned for implementation in the quarter under report.
- Column (k) *Total Planned Expenditure to Date*; the total to date amount includes a) actual expenditures for each of the works/operations implemented during past quarters, (Form B1, Column (y) of the previous QPR), and the planned expenditures for implementation of each of the works/operations planned for in the quarter under report, (Column (j) of the current QPR).

Form B2 - Planned Interventions/Works this Quarter and to Date, Columns (a) to (k)

Enter the name of the District, the number of the quarter under report and the FY.

Columns (a), (b), (c) and (d) - Enter the same information as for these same Columns in Form B1.

- Columns (e), (f), (g), (h) and (i) Routine Maintenance (RM), Periodic Maintenance (PM), Rehabilitation (RH), Road Bottlenecks (SR), and Structural Bottleneck (ST); enter the kilometres for each of the works/operations planned for implementation in the quarter under report.
 - 1. For the first QPR of the FY, Columns (e), (f), (g), (h) and (i) will use the planning data for the first quarter found in Columns (k), (l) and (m) of Form D2 of the ADRWP.
 - 2. For the second QPR of the FY, Columns (e), (f), (g), (h) and (i) will use the adjusted planning data from Columns (o), (p) and (q) found in Form B2 of the first quarter QPR.
 - 3. For the third QPR of the FY, Columns (e), (f), (g), (h) and (i) will use the adjusted planning data from Columns (r), (s) and (t) found in Form B2 of the second quarter QPR.
 - 4. For the fourth QPR of the FY, Columns (e), (f), (g), (h) and (i) will use the adjusted planning data from Columns (u), (v) and (w) found in Form B2 of the third quarter QPR.
 - 5. When preparing the fourth (end of FY) QPR, reference is also made to the ADRWP in order to <u>compare the actual</u> annual achievement, in terms of total works/operations implementation and total expenditures, <u>with that</u> <u>planned</u> in the ADRWP for the FY.
- Column (j) *Total Planned Works this Quarter*, enter the total kilometres for each of the works/ operations planned for implementation in the quarter under report.
- Column (k) *Total Planned Works to Date*, the total to date amount includes a) actual kilometres done to date for each of the works/operations implemented during past quarters, (Form B2, Column (y) of the previous QPR), and the kilometres for implementation of each of the works/operations planned for in the quarter under report, (Column (j) of the current QPR).

STEP 2

Continue to complete **Form B1** and **Form B2** together and at the same time.

Form B1 - Actual Expenditure (Ush 000) to Date and Planned Next Quarter(s)

- Columns (I) to (w) For the quarter under report, enter the actual monthly expenditures for each of the actual works/operations performed during the quarter under report and readjust the estimated costs for implementation of each of the planned works/operations over each month of the remaining period of the FY taking into account works/operations not performed during the quarter under report, time restraints related to releases of funds, the procurement process, wet season, etc..
- Column (x) *Total Actual Expenditure this Quarter*, enter the sum of the actual monthly expenditures for each of the actual works/operations performed during the quarter under report.

Section B3 District Road Manuals

Column (y) - *Total Actual Expenditure to Date*; enter the sum of the total actual expenditure to date for each of the actual works/operations performed being the sum of **Form B1**, Column (y) in the previous QPR and column (x) of the current QPR.

- In the eighth last row, *Works Expenditure*, sum the expenditures for the plan period, for each month of the quarter under report <u>and</u> those for planned subsequent months of the FY in which expenditures may have been adjusted to take account of works/operations not performed during the quarter under report.
- In the seventh last row, *Operational Expenditure*, enter the total operation expenses for the plan period, for each month of the quarter under report and subsequent months of the FY.
- In the sixth last row, *Total Expenditure*, enter the total expenditures (works plus operational) for the plan period, for each month of the quarter under report <u>and</u> those planned for subsequent months of the FY in which expenditures may have been adjusted to take account of works/operations not performed during the quarter under report.
- In the fifth last row, *Total Actual Quarterly Expenditure* (*Ush 000*)......, enter the sums of the three months actual total expenditures for the quarter under report <u>and</u> those planned for subsequent quarters of the FY.
- In the fourth last row, *Cumulative Actual Quarterly Expenditure* (Ush 000) to Date, enter the sums of actual quarterly cumulative expenditure to date.
- In the third last row, *Actual Funds Received by Quarter to Date* (*Ush 000*), enter the actual funds received during each quarter to date.
- In the second last row, *Cumulative Actual Funds Received by Quarter to Date* (Ush 000), enter the sums of actual quarterly cumulative fund receipts to date.
- In the last row, Balance of Funds Available at end this Quarter, enter the balance of the funds remaining being the difference between Cumulative Actual Funds Received by Quarter to Date (Ush 000) and the Cumulative Actual Quarterly Expenditure (Ush 000) to Date.

When completing QPRs for the second, third and fourth quarters, the information regarding actual expenditures in previous quarters remains unchanged and shall be included in subsequent QPRs thereby providing an historical overview of financial progress to date.

Form B2 - Actual Interventions/Works to Date & Planned Next Quarter(s)

- Columns (I) to (w) For the quarter under report, enter the actual monthly kilometres for each of the actual works/operations performed during the quarter under report and readjust the estimated kilometres for implementation of each of the planned works/operations over each month of the remaining period of the FY taking into account works/operations not performed during the quarter under report, time restraints related to releases of funds, the procurement process, wet season, etc..
- Column (x) *Actual Works Done this Quarter*, enter the sum of the actual monthly kilometres for each of the actual works/operations performed during the quarter under report.

- Column (y) *Actual Works Done to Date*; enter the sum of the total actual kilometres to date for each of the actual works/operations performed being the sum of **Form B2**, Column (y) in the previous QPR and column (x) of the current QPR.
- In the fifth last row, *Works Planned*, enter the kilometres planned for each of the works/operations in quarter under report.
- In the fourth, third, second and last rows, RM-km, PM-km, RH-km, SR/ST, enter data as follows-
- Column (j), enter the same figures as in fifth last row for each of the planned works/operations.
- Column (k), enter the sum of Column (y) from the previous QPR and Column (j) of the current QOR
- Columns (I) to (w), enter the total kilometres for each month of the quarter under report <u>and</u> those planned for subsequent months of the FY in which works/operations may have been adjusted to take account of works/operations not performed during the quarter under report.
- Column (x) *Actual Works Done this Quarter*, enter the sum of the actual monthly kilometres for each of the actual works/operations performed during the quarter under report.
- Column (y) *Actual Works Done to Date*, enter the sum of the total actual kilometres to date for each of the actual works/operations performed being the sum of **Form B2**, Column (y) in the previous QPR and column (x) of the current QPR.

When completing QPRs for the second, third and fourth quarters, the information regarding actual kilometres in previous quarters remains unchanged and shall be included in subsequent QPRs thereby providing an historical overview of physical progress to date.

STEP 3

On completion of Forms B1 and B2, finalise completion of Form B3 in the following manner.

Form B3 - Summary of Actual Expenditure / Fund Request

Enter the name of the District, the number of the quarter under report and the FY.

Form B3	3 comprises <u>tw</u>	<u>/o</u> Tables; the top	Table entitled	Summary of	of Actual Expen	iditure (Ush 000) to End
	Quarter of F	FY / and	the bottom Tab	ole entitled F	Fund Request ((Ush 000) for	
Quarter d	of FY /						

Form B3 - Top Table

The purpose of this Table is to report on actual expenditure for each works/operation and from each funding source during the quarter under report.

Column (M) of the Table entitled, *Total Planned Annual Expenditure*, will have been completed during January/March following the Local Government Budget Framework Process (LGBFP) at which time all sources of funding and the amounts or ceilings for each funding source will

Section B3 District Road Manuals

have been provided to the DLG Executive for preparation of the ADRWP; refer the ninth column of Form D3, *Annual Total Intervention Costs*.

For the quarter under report, relevant data is entered in columns (A) to (N) of this Table as follows.

- Column (A) *Actual Interventions/Works Done This Quarter*, lists the main works/operations included in the ADRWP together with the kilometres of each works/operation actually performed during the quarter under report. For SR/ST works, locations only are to be indicated.
- Column (B) PAF I, enter the actual expenditure for this item during the quarter under report.
- Column (C) PAF II, enter the actual expenditure for this item during the quarter under report.
- Column (D) PAF III, enter the actual expenditure for this item during the quarter under report.
- Column (E) DONOR, enter the actual expenditure for this item during the quarter under report.
- Column (F) DONOR, enter the actual expenditure for this item during the quarter under report.
- Column (G) **DISTRICT DEVELOPMENT FUND**, enter the actual expenditure for this item during the quarter under report.
- Column (H) OTHER, enter the actual expenditure for this item during the quarter under report.
- Column (I) *TOTAL ACTUAL EXPENDITURE THIS QUARTER*, enter the sum of <u>all</u> expenditures for each works/operation from each funding source for the quarter under report.
- Column (J) **TOTAL ACTUAL EXPENDITURE TO DATE**, enter the sum to date of <u>all</u> expenditures for each works/operation from each funding source; the sum of **Form B3**, Column (J) of the previous QPR plus Column (I) of the current QPR.
- Column (K) *TOTAL PAF EXPENDITURE THIS QUARTER*, enter the sum of <u>PAF Grant</u> expenditures only for each works/operation from each funding source for the guarter under report.
- Column (L) *TOTAL PAF EXPENDITURE TO DATE*, enter the sum to date of PAF <u>Grant</u> expenditures only for each works/operation from each funding source; the sum of **Form B3**, Column (L) of the previous QPR plus Column (K) of the current QPR.
- Column (M) TOTAL PLANNED ANNUAL EXPENDITURE, already complete following the LGBFP.
- Column (N) PROGRESS TO DATE %, Column (J) divided by Column (M) x 100.

The bottom part of this top Table provides a *QUARTERLY SUMMARY* listing actual expenditures during each quarter under report by their funding sources, together with quarterly and cumulative totals of <u>all</u> expenditures and <u>PAF Grant</u> only expenditures and the overall percentage progress to date.

Form B3 - Bottom Table

The purpose of this Table is to provide details of the Fund Request for the next quarter for each works/operation and from each funding source.

- Column (O) *PLANNED INTERVENTIONS/WORKS NEXT QUARTER*, lists the works/operations included in the ADRWP together with the kilometres planned for each of these works/operations in the next quarter. For SR and ST works, details of their locations only are necessary.
- Column (P) PAF I, enter the planned expenditure for the next quarter.
- Column (Q) PAF II, enter the planned expenditure for the next quarter.
- Column (R) PAF III, enter the planned expenditure for the next quarter.
- Column (S) DONOR, enter the planned expenditure for the next quarter.
- Column (T) **DONOR**, enter the planned expenditure for the next quarter.
- Column (U) *DISTRICT DEVELOPMENT FUND*, enter the planned expenditure for the next quarter.
- Column (V) *OTHER*, enter the planned expenditure for the next quarter.
- Column (W) *TOTAL PLANNED EXPENDITURE*, enter the sum of the planned expenditures for each of the works/operations from each funding source for the next quarter.

The third last row, *Sub Totals*, sums the columns of each funding source.

The second last row, *Balance Available*, details the balances available for each funding source at the end of the quarter under report.

The last row, *TOTAL FUND REQUEST NEXT QUARTER by SOURCE*, sums the columns of each funding source less the balances available.

The last row of this Table details the Total Fund Request for the Next Quarter by Source, the amounts of which will ensure achievement of the planned works/operations for the next quarter.

This information is essential for a number of reasons including -

- <u>Transparency</u> thereby ensuring the district authorities and beneficiaries of PAF Grants are fully informed regarding the sources of the funds and the amounts available; refer the PAF General and Sector Specific Guidelines concerning Public Notices
- <u>Management</u> of the funds taking into account their sources and pre-conditionalities of use; refer the PAF General and Sector Specific Guidelines
- Accountability of the funds taking into account their sources and amounts; refer the PAF General and Sector Specific Guidelines concerning required procedures
- <u>Timeliness</u> of reporting; refer the PAF General and Sector Specific Guidelines
- Accuracy to ensure the timely release of further funds.

Section B3 District Road Manuals

STEP 4

The DLGE shall maintain **Form B4**, the Contract Tracking Format, accurately and on a day-to-day basis recording each and every contractual transaction including payments, variations, etc. immediately they transpire.

Data included in the Contract Tracking Format is essential for accurate completion of **Forms B1**, **B2** and **B3** of the QPR.

The format of the Contract Tracking Format is self-explanatory and a worked example is included in **Annex 3** for further clarification.

STEP 5

Complete the QPR Covering Letter (Annex 2), ensure all attachments are included, and submit the entire document to the MoWHC-DUR Desk.

This standard format of the QPR Covering Letter is self-explanatory and a worked example is included in **Annex 3** for further clarification.

It cannot be too strongly stressed that all data required for inclusion in the three summary Tables and the list of roads be included and accurately presented. All the information necessary for completion of the three Tables is simply extracted from **Forms B1**, **B2** and **B3** for the quarter under report.

Failure to comply may very likely result in the delayed release of PAF Grants and other development funds.

The QPR shall be addressed to the Permanent Secretary, MoWHC, Entebbe, to reach him/her by no later than the last working day of the month following the end of the quarter under report.

Finally, the QPR shall be copied to the following -

- DLG Engineer, in the concerned District
- LCV Chairman, in the concerned District
- · Secretary of Works, in the concerned District
- Chairperson of the District Public Accounts Committee
- Chief Internal Auditor, in the concerned District
- RDC, in the concerned District
- Director Budget, MFPED, Kampala
- Donor Representatives (where donor funds are provided)

Worked Example

Annex 3 provides a fully worked example for preparation of a typical QPR.

Annex 1 Standard Forms including Forms B1, B2, B3 and B4

QUARTERLY PROGRESS REPORT - DISTRICT ROAD WORKS

		Total Actual	Expend. to Date	(y)																
	er(s)	Total Actual	Expend. this Qr	(x)																
-	Juarte	ırter	June	(w)																
	Next (Fourth Quarter	May	(v)																
	nned	Four	Apr	(n)																
	& Pla	ter	Mar	(t)																
FY	Date	Third Quarter	Feb	(s)																
Quarter of FY)00) to	Third	Jan	(r)																
Qua	Actual Expenditure (Ush 000) to Date & Planned Next Quarter(s)	ter	Dec	(b)																
	liture	Quart	Nov	(d)																
for	Zxpenc	Second Quarter	Oct	(0)												,				
ual B)	tual F) deS	(u)																
, Man	A	First Quarter	Aug S	(m)																
ume 3		First (July A	(1)												,				
f: Vol				D																
e (Re		Total Planned	Expend. to Date	(k)												pauu				
Expenditure Schedule (Ref: Volume 3, Manual B) for	ι 000)	Total Planned	Expend. this Qr	(j)												Fotal Actual Quarterly Expenditure (Ush 000) to Date inc. this Quarter and Planned				
diture !	Planned Expenditure this Quarter and to Date (Ush 000	Struc. Botnk	(ST)	(i)												is Quarte			(000)	
Expen	nd to I	Road Botnk	(SR)	(h)												te inc. th	to Date		ite (Ush	(-) /
	uarter a	Rehab. (RH)		(g)												0) to Dat	Ush 000)	(Osp 000)	ter to Da	ter - (+)
	e this Q	Periodc Maint.	(PM)	(f)												(Ush 00	diture (o Date (by Quar	nis Quar
	enditur	Routine Periodc Maint. Maint.	(RM)	(e)												enditure	Cumulative Actual Quarterly Expenditure (Ush 000) to Date	Actual Funds Received by Quarter to Date (Ush 000)	Cumulative Actual Funds Received by Quarter to Date (Ush 000)	Balance of Funds Available at end this Quarter - (+) / (-)
	ed Exp	Road Sect.	Len. (km)	(p)										liture		erly Exp	Quarter	ved by (Funds R	vailable
	Plann	Total Road	Len. (km)	(c)									Works Expenditure	Operational Expenditure	liture	Quart	Actual	s Recei	Actual	unds A
District:		Dist. Road	Link No.	(p)									S Expen	tional	Fotal Expenditure	Actual	lative /	l Fund	lative A	ce of Fu
Dis		Dist. Prior		(a)									Work	Opera	Total	Total.	Cumu	Actua	Cumu	Balan

Date:

(CAO)

Signed:

(DLGE)

Signed:

QUARTERLY PROGRESS REPORT - DISTRICT ROAD WORKS

		Actual Works	Done to Date	(y)													
	(s)	Actual Works	Done this Qr	(x)													
	arter	rter	June	(w)													
	ext Qu	Fourth Quarter	May	(v)													
FY	ned N	Four	Apr	(n)													
Quarter of FY	& Plar	ter	Mar	(t)													
Qua	Date	Third Quarter	Feb	(s)									-				
	rks to	Thir	Jan	(r)													
3) for	Actual Interventions/Works to Date & Planned Next Quarter(s)	rter	Dec	(b)													
nual E	ventio	Second Quarter	Nov	(d)									-				
3, Ma	I Inter	Secor	Oct	(o)													
olume	Actua	er	Sep	(u)													
Ref: V		First Quarter	Aug	(m)													
nle (First	July	(=)													
n Sched		Total Planned	Works to Date	(k)													
Works Implementation Schedule (Ref: Volume 3, Manual B) for	to Date	Total Planned	Works this Qr	(j)													
Implen		Struc. Botnk	(ST)	(i)										RM - km	PM - km	RH - km	SR/ST
Vorks	Quarte	Road Botnk	(SR)	(h)										RM	PM	RH	SF
;	ks this	Rehab. (RH)	(km)	(g)													
	ns/Wor	Periodc Maint.	(km)	(f)													
	Planned Interventions/Works this Quarter and	Road Routine Periodc Rehab. Sect. Maint. Maint. (RH)	(km)	(e)													
	ed Int	Road Sect.	Len. (km)	(p)													
	Plann	Total Road	Len. (km)	(c)									pəu				
District:		Dist. Road	Link No.	(p)									Works Planned				
Dis		Dist. Prior		(a)	1								Work				

Notes: 1. Columns (a) to (d) are same as Form B1. Columns (e) to (k), also similar to Form B1, detail Planned Interventions/Works. Columns (l) to (w) detail Actual Works Done to date and Planned. 2. Details, including locations, of SR and ST Works are detailed in Form D2

QUARTERLY PROGRESS REPORT - DISTRICT ROAD WORKS

PROG TO DATE % % PLANED ANNUAL EXPEND Quarter TOTAL - Reference Volume 3, Manual B \mathbb{A} TO DATE THIS TO QUTR (K) (L) Cum. TOTAL PAF Quarter TOTAL ACTUAL
EXPENDITURE
THIS TO
QUTR DATE
(J) (J) TO DATE Cum. Quarter Summary of Actual Expenditure (Ush 000) for Quarter of FY OTHER (H)DIST DEV FUND 9 PAF III DONOR DONOR (F) (E) 0 PAF II <u>O</u> PAF I (B) District: INTERVENTIONS/WORKS
DONE THIS QUARTER
- refer Forms B1 and B2 **QUARTERLY SUMMARY** Structure Botnk (ST) -Routine Maint (RM) -Periodic Maint (PM) -Operational Expenses TOTALS TOTALS Road Botnk (SR) -9 Second Quarter Fourth Quarter Third Quarter First Quarter Rehab (RH) -

Fund Request (Ush 000) for	st (Ush 00	00) for	Ö	Quarter of FY	FY /				
PLANNED INTERVENTIONS/WORKS -						DIST		TOTAL	
NEXT QUARTER - refer Forms B1 and B2	PAF I	PAF II	PAF III	DONOR	DONOR	DEV	OTHER	PLANNED	
						FUND		EXPENDITURE	
(0)	(P)	0	(R)	(S)	E	<u>(</u>	3	(W)	
Routine Maint (RM) -									
Periodic Maint (PM) -									
Rehab (RH) -									
Road Botnk (SR) -									
Structure Botnk (ST) -									
Operational Expenses -									
Sub Totals									
Balance Available - refer Form B1									
TOTAL FUND REQUEST NEXT QUARTER by SOURCE									

Date:

(CAO)

Signed:

(DTGE)

Signed:

QUARTERLY PROGRESS REPORT - DISTRICT ROAD WORKS

District:

to to														
Financial Progress to Date (%)	(u)													
Cumulative Payments to Date (Ush)	(m)													
Current Contract Price (Ush)	(I)													
Physical Progress to Date (%)	(k)													
Contract Time Worked (%)	(J)													
Actual Completion Date	(j)													
Scheduled Actual Completion Completion Date Date	(h)													
Date Work Actually Started	(6)													
Contract Duration (weeks)	(f)													
Date Contract Awarded	(e)													
Contract Price (Ush)	(p)													
Engineers Estimate (Ush)	(c)													
Workplan Estimate (Ush)	(q)													
Contract Number Type of Works Source of Funds	(a)													

Total Commitments to Date	Ush	J
Total Approved Annual Budget	Ush	J
Remaining Available Balance	Ush	J

Page 2

QUARTERLY PROGRESS REPORT - DISTRICT ROAD WORKS

Quarter, FY Reporting Period: District:

Notes to the above Table -

Contract Number = District No and Road No/Contract No on that road for that year/Financial Year/Type of Works - Source of Funds
 Definitions of Types of Work; RM - routine maintenance, PM - periodic maintenance, RH - rehabilitation, ST - structures,
 SR - spot repairs (inc. earthwork, minor structures and spot gravel), OT - other detailed in Explanation/Comments below
 Comments regarding individual Contract performance (refer Contract No in first Column of the above Table) 3.2
 3.3

Signed (DLGEngineer)

Dated:

Annex 2 Standard Covering Letter Format

OFFICE OF THE CHIEF ADMINISTRATIVE OFFICER DISTRICT LOCAL GOVERNMENT P.O. BOX DISTRICT

	Date:
The Permanent Secretary	
Ministry of Works, Housing and Communication	ns
P O Box 10	
Entebbe	
ATTN: P.X.E. Eng Were Higenyi Dear Sir,	
	gress Report for District Road Works Funded by PAF in
Please find herewith Quarterly Progr	ress Report for district road works in district.
	nents against planned activities for this reporting period; refer

Table A - Summary of Quarterly Progress Report - PAF

detailing planned activities and actual achievements during this reporting period.

	PLANNED		ACH	ACHIEVED		REASONS FOR
ACTIVITY	Target	Budget (a) (Ush 000)	Actual	Expend. (b) (Ush 000)	(a) - (b) (Ush 000)	VARIATIONS
1. Routine Mt						
2. Periodic Mt						
3. Rehabilitation						
4. Road						
Bottlenecks						
5. Structural						
Bottlenecks						
6. Operational /						
Undistributed Exp.						
7. Bank charges						
Totals						
	Balance at E	nd Previous Qu	arter			
	Funds Receiv	ved This Quarte	er			
	Balance Rem	naining				

Those activities planned but not undertaken during this Quarter are included in the plan for the subsequent Quarter(s) of this FY; refer Forms B1, B2, B3 and B4, attached hereto.

The list of all those roads on which works were performed during this reporting period follows; refer ADRICS Inventory data for official road names, and Form B2 of this Quarterly Progress Report -

Road	Road Name	Length Worked On (km)					(km)
No		Planned	Actual	RM	PM	RH	SR/ST

Table B below provides a cumulative summary of achievements against planned activities up to and including this reporting period; refer Annual District Road Work Plan for FY, and Forms B1, B2, B3 and B4 detailing planned activities and actual achievements during this and previous reporting periods.

Table B - Cumulative Summary of Quarterly Progress Report(s) - PAF

	PLANNED		ACHIEVED		
ACTIVITY	Target	Budget (Ush 000)	Actual	Expend. (Ush 000)	COMMENTS
Routine Mt					
2. Periodic Mt					
3. Rehabilitation					
4. Road					
Bottlenecks					
5. Structural Bottlenecks					
6. Operational /					
Undistributed Exp.					
7. Bank charges					
Totals					
	Funds Receiv	ved to Date			
	Un-spent Bal	ance Remainir	ng		
	Un-presented Cheques				
	Balance on	Bank Staten	nent		- Copy of Bank Statement Attached

Table C below provides justification for the Release Request for the next quarter; refer Forms B1, B2 and B3

Table C - Quarterly Budget Request - All Funding Sources inc. PAF

ACTIVITY	PLAN FOR QUARTER	PAF I	PAF II	PAF III	Other	TOTAL QUARTER (Ush 000)
1. Routine Maintenance						
2. Periodic Maintenance						
3. Rehabilitation						
4. Road Bottlenecks						
5. Structural Bottlenecks						
6. Operational Expenses						
	Total Budget Requirement					
	Un-spent Balance Remaining					
	Release Request for Next Quarter					

The following Attachments are included with this Quarterly Progress Report -

Note 1. If this is the First Quarterly Progress Report, then the following need to be Attachments -

- Forms D1, D2 and D3 detailing the Annual District Road Work Plan for the current FY these should have been provided with the Fourth Quarterly Progress Report of the previous FY; refer Note 3. below
- Form B1 Expenditure Schedule detailing actual spending during this Quarter and planned spending for the remainder of this FY
- Form B2 Works Implementation Schedule detailing actual works done this Quarter and planned for the remainder of this FY
- Form B3 Summary of Actual Expenditure during this Quarter together with the Fund Request for the following Quarter
- Form B4 Quarterly Progress Report detailing all district road works undertaken during this Quarter and planned for the remainder of this FY
- Bank Statement detailing all transactions during and to the end of this quarter

Note 2. If this is the Second and Third Quarterly Progress Reports, then the following need to be Attachments -

- Form B1 Expenditure Schedule detailing actual spending during this Quarter and planned spending for the remainder of this FY
- Form B2 Works Implementation Schedule detailing actual works done this Quarter and planned for the remainder of this FY
- Form B3 Summary of Actual Expenditure during this Quarter together with the Fund Request for the following Quarter
- Form B4 Quarterly Progress Report detailing all district road works undertaken during this Quarter and planned for the remainder of this FY
- Bank Statement detailing all transactions during and to the end of this quarter

Note 3. If this is the Fourth Quarterly Progress Report, the list of Attachments will be as follows;

- Forms B1, B2, B3 and B4 for the last Quarter of the current FY including, in Form B3, the Fund Request for the following Quarter which will be the first quarter of the next FY
- Form D1 Annual District Road Work Plan for next FY, detailing the Expenditure Schedule for those works planned for implementation during the FY
- Form D2 Annual District Road Work Plan for the next FY, detailing the Works Implementation Schedule or programme for all those works planned during the FY
- Form D3 Annual District Road Work Plan for the next FY, detailing, for each of the works to be performed, the funding required, its source of origin, and the planned schedule for quarterly Fund Releases to ensure achievement of the works programme
- Bank Statement detailing all transactions during and to the end of this quarter

Yours sincerely,

Annex 3 Worked Example

OFFICE OF THE CHIEF ADMINISTRATIVE OFFICER DISTRICT LOCAL GOVERNMENT P.O. BOX DISTRICT

	Date:

The Permanent Secretary Ministry of Works, Housing and Communications P O Box 10 Entebbe

ATTN: P.X.E. Eng Were Higenyi

Dear Sir,

RE: Submission ofFirst... Quarterly Progress Report for District Road Works Funded by PAF inLira...... District for Financial Year / / Please find herewithFirst..... Quarterly Progress Report for district road works inLira..... district.

Table A below provides a summary of achievements against planned activities for this reporting period; refer Annual District Road Work Plan for FY /, and Forms B1, B2, B3 and B4, attached hereto, detailing planned activities and actual achievements during this reporting period.

Table A - Summary of Quarterly Progress Report - PAF

	PLAN	NNED	ACHI	EVED	VARIATION	REASONS FOR
ACTIVITY	Target	Budget (a) (Ush 000)	Actual	Expend. (b) (Ush 000)	(a) - (b) (Ush 000)	VARIATIONS
Routine Mt Periodic Mt	56 km	24,960	44 km 0	15,700	- 9,260 0	The first release of funds for this FY were delayed
3. Rehabilitation	0	0	0	0	0	and not received in the
4. Road Bottlenecks	0	0	0	0	0	district until late July thereby delaying the start
5. Structural Bottlenecks	0	0	0	0	0	of works; particularly routine maintenance.
6. Operational / Undistributed Exp.	Procurement activities	11,000	Procurement activities	8,000	- 3,000	Also Budget received was less than planned and
7. Bank charges	-	0	-	0	0	requested.
Totals	Budget	35,960	Expend.	23,700	- 12,260	
	Balance at End Previous Quarter			0		•
	Funds Received This Quarter			25,000		
	Balance Rem	aining	·	1,300		

Those activities planned but not undertaken during this Quarter are included in the plan for the subsequent Quarter(s) of this FY; refer Forms B1, B2, B3 and B4, attached hereto.

The list of all those roads on which works were performed during this reporting period follows; refer ADRICS Inventory data for official road names, and Form B2 of this Quarterly Progress Report -

Road	Road Name	Length Wor	ked On (km)	Туре	of Wor	ks Done	(km)
No		Planned	Actual	RM	PM	RH	SR/ST
2201	mmm - (full official name as per Inventory)	6	4	4			
2204	kkk	5	4	4			
2207	000	5	4	4			
2208	uuu	5	4	4			
2202	ttt	5	4	4			
2203	ddd	5	4	4			
2206	SSS	5	4	4			
2205	eee	5	4	4			
2211	VVV	5	4	4			
2209	ууу	5	4	4			
2210	mmm	5	4	4			
	Totals (km)	56	44	44	0	0	

Table B below provides a cumulative summary of achievements against planned activities up to and including this reporting period; refer Annual District Road Work Plan for FY, and Forms B1, B2, B3 and B4 detailing planned activities and actual achievements during this and previous reporting periods.

Table B - Cumulative Summary of Quarterly Progress Report(s) - PAF

	PLAN	NED	ACHI	EVED	
ACTIVITY	Target	Budget (Ush 000)	Actual	Expend. (Ush 000)	COMMENTS
Routine Mt	56 km	24,960	44 km	15,700	
2. Periodic Mt	0	0	0	0	
3. Rehabilitation	0	0	0	0	
4. Road Bottlenecks	0	0	0	0	
5. Structural Bottlenecks	0	0	0	0	
6. Operational / Undistributed Exp.	Procurement activities	11,000	Procurement activities	8,000	
7. Bank charges	-	0	-	0	
Totals	Budget	35,960	Expend.	23,700	
	Funds Receiv	red to Date		25,000	
	Un-spent Bal	ance Remainin	ıg	1,300	
	Un-presented	Cheques		0	
	Balance on	Bank Staten	nent	1,300	- Copy of Bank Statement Attached

Table C below provides justification for the Release Request for the next quarter; refer Forms B1, B2 and B3

Table C - Quarterly Budget Request - All Funding Sources inc. PAF

ACTIVITY	PLAN FOR QUARTER	PAF I	PAF	PAF	Other	TOTAL
			II	III		QUARTER
						(Ush 000)
1. Routine Maintenance	66 km	28,390	0	0	0	28,390
2. Periodic Maintenance	7 km	0	60,000	0	0	60,000
3. Rehabilitation	nil	0	0	0	0	0
4. Road Bottlenecks	Locations A and C, 800 lm embankment fill	0	0	0	11,000	11,000
5. Structural Bottlenecks	nil	0	0	0	0	0
6. Operational Expenses	Preparation contract doc's, and procurement	4,000	4,000	4,000	0	12,000
	Total Budget Requirement	32,390	64,000	4,000	11,000	111,390
	Un-spent Balance Remaining	1,300	0	0	0	1,300
	Release Request for Next Quarter	31,090	64,000	4,000	11,000	110,090

The following Attachments are included with this Quarterly Progress Report -

Note 1. If this is the First Quarterly Progress Report, then the following need to be Attachments -

- Forms D1, D2 and D3 detailing the Annual District Road Work Plan for the current FY these should have been provided with the Fourth Quarterly Progress Report of the previous FY; refer Note 3. below
- Form B1 Expenditure Schedule detailing actual spending during this Quarter and planned spending for the remainder of this FY
- Form B2 Works Implementation Schedule detailing actual works done this Quarter and planned for the remainder of this FY
- Form B3 Summary of Actual Expenditure during this Quarter together with the Fund Request for the following Quarter
- Form B4 Quarterly Progress Report detailing all district road works undertaken during this Quarter and planned for the remainder of this FY
- Bank Statement detailing all transactions during and to the end of this quarter

Note 2. If this is the Second and Third Quarterly Progress Reports, then the following need to be Attachments -

- Form B1 Expenditure Schedule detailing actual spending during this Quarter and planned spending for the remainder of this FY
- Form B2 Works Inplementation Schedule detailing actual works done this Quarter and planned for the remainder of this FY
- Form B3 Summary of Actual Expenditure during this Quarter together with the Fund Request for the following Quarter
- Form B4 Quarterly Progress Report detailing all district road works undertaken during this Quarter and planned for the remainder of this FY
- Bank Statement detailing all transactions during and to the end of this quarter

Note 3. If this is the Fourth Quarterly Progress Report, the list of Attachments will be as follows;

- Forms B1, B2, B3 and B4 for the last Quarter of the current FY including, in Form B3, the Fund Request for the following Quarter which will be the first quarter of the next FY
- Form D1 Annual District Road Work Plan for next FY, detailing the Expenditure Schedule for those works planned for implementation during the FY
- Form D2 Annual District Road Work Plan for the next FY, detailing the Works Implementation Schedule or programme for all those works planned during the FY
- Form D3 Annual District Road Work Plan for the next FY, detailing, for each of the works to be performed, the funding required, its source of origin, and the planned schedule for quarterly Fund Releases to ensure achievement of the works programme
- Bank Statement detailing all transactions during and to the end of this quarter

Yours sincerely,

Chief Administrative Officer

....Lira..... District Local Government

CC DLG Engineer,Lira....... District
LCV Chairman,Lira....... District
Sec. of Works,Lira....... District
Chairperson of the District Public Accounts Committee,
Chief Internal Auditor,

RDC,District

Director Budget, MFPED, Kampala

Donor Representative (s) - in all cases where donor funds are provided

Total Actual Expend. 2,000

3

1,200

1,750

1,000

2,000

QUARTERLY PROGRESS REPORT - DISTRICT ROAD WORKS

ı	Actual Expenditure (Ush 000) to Date & Planned Next Quarter(s)	Fourth Quarter Total Actual	May June Expend.	(x) (w) (x)	1,150 1,300 2,000	0	800 1,200 1,200	0	1.070 1,030 1,750	0	0	700 700 1,000	25,000 18,750 0	1,200 1,200 2,000	800 900 1,400	610 640 1,000	670 680 1,100	1,100 1,200 1,850	860 840 1,400	630 650 1,000	34,590 29,090 15,700	4,000 4,000 8,000	590 33,090 23,700	120,270 494		
	nned No	Fourth	Apr N	(n)	1,150 1		800		1,070 1		35,000	700	25	1,200	800	610	029	1,100 1	098	630	44,590 34	4,000 4	71,090 48,590 38,590	12(
	e & Pla	rter	Mar	(£)	1,150		800		1,070	22,500	35,000	700		1,200	800	610	029	1,100	098	630	67,090	4,000				
FY	to Date	Third Quarter	Feb	(s)	5,000		7,000	35,000	5,000	30,000						1,500			1,500		85,000	4,000	89,000	239,590		
	(000 H	Thi	Jan	(r)	5,000	0 27,500	5,000	35,000	0			0		3,000	0	0	0	0	0	0	0 15,500	000,4	79,500			
<u>First</u> Quarter of	ıre (Us	uarter	Dec	(b)	0 6,250	0 30,000	0 6,700		0 1,070			00 200		0 1,200	008 0	0 610	0.00	0 1,050	098 0	0 620	0 50,530	0 4,000	0 54,530	06		
	pendit	Second Quarter	Nov	(d)	50 1,150	30,000	700 700		70 1,070			700 700		00,1,200	008 008	610 610	029 029	50 1,050	098 098	620 620	30 39,430	000,4	30 43,430	111,390		
(Ref: Volume 3, Manual B) for	ual Ex	Š	p Oct	(0)	1,000 1,150		009		900 1,070			500		1,000 1,200	700 80	9 009	9 055	950 1,050	700 86	200 005	00 9,430	000 4,000	00 13,430			
Manu	Act	uarter	deS gi	(n) (r	1,000 1,0		9 009		6 058			5 005		1,000 1,0	7007	5 005	550 5	6 006	7007	500	7,800 7,900	2,500 3,500	300 11,400	00,	00,	000
ume 3,		First Quarter	July Aug	(m) (m)	1,(~			4,		1,(7,	4,	J.		7,	0 7,8	2,000 2,5	2,000 10,300	23,700	23,700	25,000
ef: Vol		al ned			3,090	0	2,070	0	2,760	0	0	1,770	0	3,120	2,130	1,590	1,740	2,850	2,220	1,620	24,960	11,000 2,	35,960 2,			
			Expend. to Date	(k)		С		С		0	0		0											anned		
re Schedule	(Osh 000)	Total Planned	Expend. this Qr	(j)	3,090		2,070		2,760			1,770		3,120	2,130	1,590	1,740	2,850	2,220	1,620	24,960	11,000	35,960	uarter and Planned		
		Struc. Botnk	(ST)	(i)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	s Quart		
Expenditu	nd to D	Road Botnk	(SR)	(h)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	e inc. thi	to Date	
=	narter a	Rehab. (RH)		(g)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	3,845	3,845) to Dat	Sh 000)	Jsh 000)
	this Qu	Periodc Maint.	(PM)	(f)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	4,488	4,488	(Ush 000	diture (I	Date (I
	Planned Expenditure this Quarter and to Date	υ.	(RM)	(e)	3,090	0	2,070	0	2,760	0	0	1,770	0	3,120	2,130	1,590	1,740	2,850	2,220	1,620	24,960	2,668	27,628	otal Actual Quarterly Expenditure (Ush 000) to Date inc. this Q	umulative Actual Quarterly Expenditure (Ush 000) to Date	ctual Funds Received by Quarter to Date (Ush 000)
	ed Exp	Road Sect.	Len. (km)	(p)	23.50	10.00	15.75	5.00	21.00	00.9	5.00	13.50	5.00	23.80	16.30	12.20	13.00	21.70	16.90	12.30		iture		rly Exp	Juarter	ed by C
	Plann	Total Road	Len. (km)	(c)	23.50	23.50	20.75	20.75	26.00	26.00	26.00	13.50	13.50	23.80	16.30	12.20	13.00	21.70	16.90	12.30	nditure	perational Expenditure	liture	Quarte	Actual (s Receiv
District:		Dist. Road	Link No.	(p)	2201	2201	2204	2204	2207	2207	2207	2208	2208	2202	2203	2206	2205	2211	2209	2210	orks Expenditure	ational	otal Expenditure	Actual	ulative .	al Fund
Dis		ist. rior		(a)	1		2	2	3	3	3	4	4	5	9	7	~	6	10	11	ork	per	otal	otal	nmı	ctus

1,850 1,400 1,000

8,000 23,700

026

Date:

(CAO)

Signed:

(Sec. of Works)

Signed:

(DLGE)

Signed:

+ 1,300

Balance of Funds Available at end this Quarter - (+) / (-)

1,000

		Actual Works	Done to Date	(y)	4	0	4	0	4	0	0	4	0	4	4	4	4	4	4	4		44	0	0	0
	(s)	Actual Works	Done this Qr	(x)	4	0	4	0	4	0	0	4	0	4	4	4	4	4	4	4	-	44	0	0	0
	Actual Interventions/Works to Date & Planned Next Quarter(s)	rter	June	(w)	1.50	0	0.75	0	2	0	0	0.50	3	2.80	1	0.50	0	2.70	06.0	0.50	-	13.15	2	0	0
	Vext Q	Fourth Quarter	May	(v)	4	0	1	0	3	0	0	1	2	3	1.30	0.50	1	3	2	0.50		20.30	3	0	0
FY	uned №	Four	Apr	(n)	4	0	2	0	3	0	3	1	0	4	2	0.50	1	3	2	0.50		23	0	3	0
er of	& Pla	rter	Mar	(t)	4	0	2	0	3	3	2	1	0	4	2	0.70	1	3	2	08.0	-	23.5	3	2	0
<u>First</u> Quarter of FY) Date	Third Quarter	Feb	(s)	0/B	0	0/D	3	0/E	3	0	0	0	0	0	9/0	0	0	H/0	0	-	0	3	3	Е,G,Н
First	orks to	Thi	Jan	(r)	0/B	3	Q/D	2	0	0	0	0	0	J/0	0	0	0	0	0	0		0	3	2	B,D,F
(Ref: Volume 3, Manual B) for	ons/W	arter	Dec	(b)	2/A	4	2/C	0	2	0	0	2	0	2	2	2	7	7	7	7		22	4	0	A,C
Ianual	rventi	Second Quarter	Nov	(d)	2	3	2	0	2	0	0	2	0	2	2	2	7	7	7	7		22	3	0	0
ne 3, IV	al Inte	Seco	Oct	(0)	2	0	2	0	2	0	0	2	0	2	2	2	2	2	2	2		22	0	0	0
Volun	Actu	ter	Sep	(u)	2	0	2	0	2	0	0	2	0	2	2	2	2	2	2	2		22	0	0	0
(Ref:		First Quarter	Aug	(m)	2	0	2	0	2	0	0	2	0	2	2	2	2	2	2	2		22	0	0	0
dule		Fir	July	(I)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0
on Sche		Total Planned	Works to Date	(k)	9	0	5	0	5	0	0	5	0	5	5	5	5	5	5	5		99	0	0	0
Works Implementation Schedule	Date	Total Planned	Works this Qr	(j)	9	0	5	0	5	0	0	5	0	5	5	5	5	5	5	5		99	0	0	0
Imple	and to	Struc. Botnk	(ST)	(i)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	- km	- km	- km	ST
Vorks	Quarter	Road Botnk	(SR)	(h)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	RM -	- MA	RH -	SR / ST
	ks this (Rehab. (RH)	(km)	(g)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
	ns/Wor	Periodc Maint.	(km)	(f)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
	Planned Interventions/Works this Quarter and to Date	o .	(RM)	(e)	9	0	5	0	5	0	0	5	0	5	5	5	5	5	5	5	99				
	ed Int	Road Sect.	Len. (km)	(p)	23.50	10.00	15.75	5.00	21.00	00.9	5.00	13.50	5.00	23.80	16.30	12.20	13.00	21.70	16.90	12.30					
	Plann		Len. (km)	(c)	23.50	23.50	20.75	20.75	26.00	26.00	26.00	13.50	13.50	23.80	16.30	12.20	13.00	21.70	16.90	12.30	pa				
District:			Link No.	(p)	2201	2201	2204	2204	2207	2207	2207	2208	2208	2202	2203	2206	2205	2211	2209	2210	Vorks Planned				
Dist		Dist.		(a)	1	1	2	2	3	3	3	4	4	5	9	7	8	6	10	11	Vorks				

Notes: 1. Columns (a) to (d) are same as Form B1. Columns (e) to (k), also similar to Form B1, detail Planned Interventions/Works. Columns (l) to (w) detail Actual Works Done to date and Planned. 2. Details, including locations, of SR and ST Works are detailed in Form D2

Date: (CAO) Signed: (Sec. of Works) Signed: (DLGE) Signed:

District:

Summary of Actual Expenditure (Ush 000) or FIRST Ouarter of FY

- Reference Volume 3. Manual B

Summary of factual Experiments (Sm 600) of Times	T TACKER	244					Z Tuny	LI IO IOIDA			cc volunic	Included volume 3, intainal D	
ACTUAL						DIST		TOTAL ACTUAL	ACTUAL	TOTAL PAF	L PAF	TOTAL	PROG
INTERVENTIONS/WORKS	PAF I	PAF II	PAF III DONOR	DONOR	DONOR	DEV	OTHER	EXPENDITURE	MITURE	EXPENDITURE	DITURE	PLANED	OL
DONE THIS QUARTER				Danida	USAID	FUND		SIHL	10	SIHL	OL	ANNUAL	DATE
- refer Forms B1 and B2								QUTR	DATE	QUTR	DATE	EXPEND	%
(A)	(B)	(C)	(D)	(E)	(F)	(G)	(H)	(I)	(J)	(K)	(L)	(M)	(N)
Routine Maint (RM) - 44 KM	15,700	0	0	0	0	0	0	15,700	15,700	15,700	15,700	83,200	19
Periodic Maint (PM) - NIL	0	0	0	0	0	0	0	0	0	0	0	183,750	0
Rehab (RH) - NIL	0	0	0	0	0	0	0	0	0	0	0	140,000	0
Road Botnk (SR) - NIL	0	0	0	0	0	0	0	0	0	0	0	11,000	0
Structure Botnk (ST) - NIL	0	0	0	0	0	0	0	0	0	0	0	33,000	0
Operational Expenses	2,000	2,500	3,500	0	0	0	0	8,000	8,000	8,000	8,000	44,000	18
TOTALS	17,700	2,500	3,500	0	0	0	0	23,700	23,700	23,700	23,700	494,950	5
QUARTERLY SUMMARY								Quarter	Cum.	Quarter	Cnm.	Quarter	%
First Quarter	17,700	2,500	3,500	0	0	0	0	23,700	23,700	23,700	23,700	35,960	99
Second Quarter												106,960	
Third Quarter												237,320	
Fourth Quarter												114,710	
TOTALS	17,700	2,500	3,500	0	0	0	0	23,700	23,700	23,700	23,700	494,950	5

Fund Request (Ush 000) for SECOND Quarter of FY

PLANNED INTERVENTIONS/WORKS -						DIST		TOTAL
NEXT QUARTER - refer Forms B1 and B2	PAF I	PAF II	PAF III	DONOR	DONOR	DEV	OTHER	PLANNED
				Danida	USAID	FUND		EXPENDITURE
(0)	(P)	0	(R)	(S)	(L)	9	3	(W)
Routine Maint (RM) - 66 KM	28,390	0	0	0	0	0	0	28,390
Periodic Maint (PM) - 7 KM	0	60,000	0	0	0	0	0	000'09
Rehab (RH) - NIL	0	0	0	0	0	0	0	0
Road Botnk (SR) - Locations A and C	0	0	0	0	11,000	0	0	11,000
Structure Botnk (ST) - NIL	0	0	0	0	0	0	0	0
Operational Expenses - Preparation contract doc's / procurement	4,000	4,000	4,000	0	0	0	0	12,000
Sub Totals	32,390	64,000	4,000	0	11,000	0	0	111,390
Balance Available - refer Form B1	1,300	0	0	0	0	0	0	
TOTAL FUND REQUEST NEXT QUARTER by SOURCE	31,090	64,000	4,000	0	11,000	0	0	

Signed:

(DLGE)

(Sec. of Works) Signed:

Signed:

(CAO)

Date:

District:

Reporting Period: FIRST Quarter, FY / Page 1

0																										
Financial Progress to Date (%)	(u)	19				11				19				11		19		20	19		19	19	19		19	
Cumulative Payments to Date (Ush)	(m)	2,000,000				1,200,000				1,750,000				1,000,000		2,000,000		1,400,000	1,000,000		1,100,000	1,850,000	1,400,000		1,000,000	15,700,000
Current Contract Price (Ush)	(1)	10,300,000				6,900,000				9,200,000				5,900,000		10,400,000		7,100,000	5,300,000		5,800,000	9,500,000	7,400,000		5,400,000	83,200,000
Physical Progress to Date (%)	(k)	20				20				25				20		20		20	20		20	20	20		20	
Contract Time Worked (%)	(<u>l</u>)	22				22				22				22		22		22	22		22	22	22		22	
Actual Completion Date	(<u>i</u>)																									
Scheduled Actual Completion Completion Date Date	(h)	30/06/02				30/06/02				30/06/02				30/06/02		30/06/02		30/06/02	30/06/02		30/06/02	30/06/02	30/06/02		30/06/02	
Date Work Actually Started	(b)	04/08/01				05/08/01				04/08/01				03/08/01		03/08/01		03/08/01	04/08/01		03/08/01	03/08/01	03/08/01		03/08/01	
Contract Duration (weeks)	(f)	40				40				40				40		40		40	40		40	40	40		40	
Date Contract Awarded	(e)	02/07/01				02/07/01				02/07/01				02/07/01		02/07/01		03/07/01	03/07/01		03/07/01	03/07/01	03/07/01		03/07/01	
Contract Price (Ush)	(p)	10,300,000				6,900,000				9,200,000				5,900,000		10,400,000		7,100,000	5,300,000		5,800,000	9,500,000	7,400,000		5,400,000	83,200,000
Engineers Estimate (Ush)	(c)	10,300,000	87,500,000	5,000,000	10,000,000	6,900,000	70,000,000	6,000,000	12,000,000	9,200,000	52,500,000	70,000,000	5,000,000	5,900,000	43,750,000	10,400,000	3,000,000	7,100,000	5,300,000	1,500,000	5,800,000	9,500,000	7,400,000	1,500,000	5,400,000	450,950,000
Workplan Estimate (Ush)	(q)	10,300,000	87,500,000	5,000,000	10,000,000	6,900,000	70,000,000	6,000,000	12,000,000	9,200,000	52,500,000	70,000,000	5,000,000	5,900,000	43,750,000	10,400,000	3,000,000	7,100,000	5,300,000	1,500,000	5,800,000	9,500,000	7,400,000	1,500,000	5,400,000	450,950,000
Contract Number Type of Works Source of Funds	(a)	2201/01/0102/RM - PAF I	2201/02/0102/PM - PAF II	2201/03/0102/SR - Donor	2201/04/0102/ST - Donor	2204/01/0102/RM - PAF I	2204/02/0102/RH - PAF III	2204/03/0102/SR - Donor	2204/04/0102/ST - Donor	2207/01/0102/RM - PAF I	2207/02/0102/PM - PAF II	2207/03/0102/RH - PAF III	2207/04/0102/ST - Donor	2208/01/0102/RM - PAF I	2208/02/0102/PM - PAF II	2202/01/0102/RM - PAF I	2202/02/0102/ST - Donor	2203/010102/RM - PAF I	2206/01/0102/RM - PAF I	2206/02/0102/ST - Donor	2205/01/0102/RM - PAF I	2211/01/0102/RM - PAF I	2209/01/0102/RM - PAF I	2209/02/0102/ST - Donor	2210/01/0102/RM - PAF I	

83,200,000	450,950,000	367,750,000
Ush	Ush	Ush
Total Commitments to Date	Total Approved Annual Budget	Remaining Available Balance

District:

Notes to the above Table -

Contract Number = District No and Road No/Contract No on that road for that year/Financial Year/Type of Works - Source of Funds
 Definitions of Types of Work; RM - routine maintenance, PM - periodic maintenance, RH - rehabilitation, ST - structures,
 SR - spot repairs (inc. earthwork, minor structures and spot gravel), OT - other detailed in Explanation/Comments below

Comments regarding Contract performance (refer Contract Ref. No in above Table) First Fund Release delayed till end July. As a result no contracts could be signed until early August

Signed (DLGEngineer)

Dated:

OFFICE OF THE CHIEF ADMINISTRATIVE OFFICER DISTRICT LOCAL GOVERNMENT P.O. BOX DISTRICT

	Date:
	Permanent Secretary stry of Works, Housing and Communications
	Box 10
Entel	bbe
ATT Dear	N: P.X.E. Eng Were Higenyi Sir,
RE:	Submission ofSecond Quarterly Progress Report for District Road Works Funded by PAF inLira District for Financial Year
Pleas	e find herewithSecond Quarterly Progress Report for district road works inLira district.
Annu	e A below provides a summary of achievements against planned activities for this reporting period; refer all District Road Work Plan for FY

Table A - Summary of Quarterly Progress Report - PAF

	PLAN	LANNED ACHII		EVED	VARIATION	REASONS FOR
ACTIVITY	Target	Budget (a) (Ush 000)	Actual	Expend. (b) (Ush 000)	(a) - (b) (Ush 000)	VARIATIONS
Routine Mt	66 km	28,390	64 km	28,770	390 (overspent)	
2. Periodic Mt	7 km	60,000	6 km	56,600	3,400	
3. Rehabilitation	0	0	0	0	0	
4. Road Bottlenecks	(A, C)	(11,000)	(A, C)	(11,000)	0	
5. Structural Bottlenecks	0	0	0	0	0	
6. Operational / Undistributed Exp.	Procurement activities	12,000	Procurement activities	11,000	1,000	
7. Bank charges	-	0	-	0	0	
Totals	Budget	100,390	Expend.	96,370	4,010	
	Balance at End Previous Quarter			1,300		
	Funds Received This Quarter			104,000		
	Balance Rem	aining		8,930		

Those activities planned but not undertaken during this Quarter are included in the plan for the subsequent Quarter(s) of this FY; refer Forms B1, B2, B3 and B4, attached hereto.

The list of all those roads on which works were performed during this reporting period follows; refer ADRICS Inventory data for official road names, and Form B2 of this Quarterly Progress Report -

Road	Road Name	Length Wor	Length Worked On (km)			Type of Works Done (km)				
No		Planned	Actual	RM	PM	RH	SR/ST			
2201	mmm - (full official name as per Inventory)	13	12	6	6		A			
2204	kkk	6	6	6			C			
2207	000	6	6	6						
2208	uuu	6	6	6						
2202	ttt	6	6	6						
2203	ddd	6	5	5						
2206	SSS	6	6	6						
2205	eee	6	5	5						
2211	VVV	6	6	6						
2209	ууу	6	6	6						
2210	mmm	6	6	6						
	Totals (km)	73	70	64	6	0				

Table B below provides a cumulative summary of achievements against planned activities up to and including this reporting period; refer Annual District Road Work Plan for FY, and Forms B1, B2, B3 and B4 detailing planned activities and actual achievements during this and previous reporting periods.

Table B - Cumulative Summary of Quarterly Progress Report(s) - PAF

	PLAN	NED	ACHI	EVED	
ACTIVITY	Target	Budget (Ush 000)	Actual	Expend. (Ush 000)	COMMENTS
Routine Mt	110 km	44,090	108 km	44,470	PAF I
2. Periodic Mt	7 km	60,000	6 km	56,600	PAF II
Rehabilitation	0	0	0	0	
4. Road	(A, C)	(11,000)	(A, C)	(11,000)	Funding for these road bottlenecks was
Bottlenecks					provided by donor - USAID
Structural	0	0	0	0	
Bottlenecks					
6. Operational /	Procurement	20,000	Procurement	19,000	PAF
Undistributed Exp.	activities		activities		
Bank charges	-	0	ı	0	
Totals	Budget	124,090	Expend.	120,070	
	Funds Receiv	ed to Date		129,000	
	Un-spent Balance Remaining Un-presented Cheques			8,930	
				0	
	Balance on	Bank Staten	nent	8,930	- Copy of Bank Statement Attached

Table C below provides justification for the Release Request for the next quarter; refer Forms B1, B2 and B3

Table C - Quarterly Budget Request - All Funding Sources inc. PAF

ACTIVITY	PLAN FOR QUARTER	PAF I	PAF II	PAF	Other	TOTAL
				III		QUARTER
						(Ush 000)
1. Routine Maintenance	23.5 km	9,665				9,665
2. Periodic Maintenance	10 km	0	83,400			83,400
3. Rehabilitation	7 km	0		105,000		105,000
4. Road Bottlenecks	nil	0				0
5. Structural Bottlenecks	Locations B, D, E, F, G and H	0			33,000	33,000
6. Operational Expenses	Procurement and supervision	4,000	4,000	4,000	0	12,000
	Total Budget Requirement	13,665	87,400	109,000	33,000	243,065
	Un-spent Balance Remaining	2,000	3,000	3,930	0	8,930
	Release Request for Next Qurt	11,665	84,400	105,070	33,000	234,135

The following Attachments are included with this Quarterly Progress Report -

Note 1. If this is the First Quarterly Progress Report, then the following need to be Attachments -

- Forms D1, D2 and D3 detailing the Annual District Road Work Plan for the current FY these should have been provided with the Fourth Quarterly Progress Report of the previous FY; refer Note 3. below
- Form B1 Expenditure Schedule detailing actual spending during this Quarter and planned spending for the remainder of this FY
- Form B2 Works Implementation Schedule detailing actual works done this Quarter and planned for the remainder of this FY
- Form B3 Summary of Actual Expenditure during this Quarter together with the Fund Request for the following Quarter
- Form B4 Quarterly Progress Report detailing all district road works undertaken during this Quarter and planned for the remainder of this FY
- Bank Statement detailing all transactions during and to the end of this quarter

Note 2. If this is the Second and Third Quarterly Progress Reports, then the following need to be Attachments -

- Form B1 Expenditure Schedule detailing actual spending during this Quarter and planned spending for the remainder of this FY
- Form B2 Works Inplementation Schedule detailing actual works done this Quarter and planned for the remainder of this FY
- Form B3 Summary of Actual Expenditure during this Quarter together with the Fund Request for the following Quarter
- Form B4 Quarterly Progress Report detailing all district road works undertaken during this Quarter and planned for the remainder of this FY
- Bank Statement detailing all transactions during and to the end of this quarter

Note 3. If this is the Fourth Quarterly Progress Report, the list of Attachments will be as follows;

- Forms B1, B2, B3 and B4 for the last Quarter of the current FY including, in Form B3, the Fund Request for the following Quarter which will be the first quarter of the next FY
- Form D1 Annual District Road Work Plan for next FY, detailing the Expenditure Schedule for those works planned for implementation during the FY
- Form D2 Annual District Road Work Plan for the next FY, detailing the Works Implementation Schedule or programme for all those works planned during the FY
- Form D3 Annual District Road Work Plan for the next FY, detailing, for each of the works to be
 performed, the funding required, its source of origin, and the planned schedule for quarterly Fund Releases
 to ensure achievement of the works programme
- Bank Statement detailing all transactions during and to the end of this quarter

Yours sincerely,

Chief Administrative OfficerLira..... District Local Government

CC DLG Engineer,Lira........ District
LCV Chairman,Lira......... District
Sec. of Works,Lira......... District
Chairperson of the District Public Accounts Committee,
Chief Internal Auditor,
RDC,Lira......... District
Director Budget, MFPED, Kampala
Donor Representative (s) - in all cases where donor funds are provided

(Ref: Volume 3, Manual B) for Second Quarter of FY
Expenditure Schedule
District:

	Plai	nned Ex	Planned Expenditure this Quarter and to Date (Ush 000)	e this Qu	uarter a	nd to Da	ate (Ush	(000)			A	ctual E	xpend	Actual Expenditure (Ush 000) to Date & Planned Next Quarter(s)	sh 000) to Da	te & Pl	lanned	Next C	Juarte	r(s)	
Dist. D	Dist. Total	al Road	Routine	Periodc	Rehab.	Road	Struc.	Total	Total	First	First Quarter		Second	Second Quarter		Third Quarter	arter	Four	Fourth Quarter	rter	Total	Total
Prior R				Maint.	(RH)	Botnk	u	Planned	Planned		ı			ı		,			,			Actual
	Link Len. No. (km)	l. Len.	(RM)	(PM)		(SR)	(ST)	Expend. this Qr	Expend. to Date	July	S gny	O dəs	Oct N	Nov Dec	c Jan	Feb	Mar	Apr	May	June	Expend. I	Expend. to Date
(a) ((p) (c)	(p)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(1)	(m)	(u)	I) (o)	(b) (d)	(r)	(s)	(£)	(n)	(v)	(w)	(x)	(y)
1 2.	2201 23.50	0 23.50	3,550	0	0	5,000	0	8,550	10,550		1,000 1	1,000 1,	1,100 1,	1,150 6,300	000 5,000	000'5 00	0 1,180	1,190	1,190	1,200	8,550	10,550
1 2.	2201 23.50	0 10.00	0	60,000	0	0	0	60,000	60,000				25,	25,600 31,000	00 30,900	0.					56,600	56,600
2 2	2204 20.75	5 15.75	2,100	0	0	6,000	0	8,100	9,300		009	009	200	700 6,700	000 5,000	000',	006 0	006 (006	006	8,100	9,300
2 2	2204 20.75	5 5.00	0	0	0	0	0	0	0						35,000	000'58'000	0				0	0
3 22	2207 26.00	0 21.00	3,210	0	0	0	0	3,210	4,960		850	900 1,	1,070 1,	1,070 1,070	70	5,000	0 1,060	1,060	1.060	1,060	3,210	4,960
3 22	2207 26.00	00.9 0	0	0	0	0	0	0	0							30,000	0 22,500				0	0
3 22	2207 26.00	0 5.00	0	0	0	0	0	0	0								35,000	35,000			0	0
4 22	2208 13.50	0 13.50	2,100	0	0	0	0	2,100	3,100		200	200	200	700	200		700	00/	700	700	2,100	3,100
4 22	2208 13.50	0 5.00	0	0	0	0	0	0	0										25,000	18,750	0	0
5 22	2202 23.80	0 23.80	3,600	0	0	0	0	3,600	5,600		1,000 1	1,000 1,	,200 1,	,200 1,20	,200 3,000	0.	1,200	1,200	1,200	1,200	3,600	5,600
6 22	2203 16.30	0 16.30	2,400	0	0	0	0	2,400	3,800		700	200	800	800	800		825	825	825	825	2,400	3,800
7 22	2206 12.20	0 12.20	1,830	0	0	0	0	1,830	2,830		200	200	009	9 029	630	1,500	009 0	009 (009	059	1,850	2,850
8 2.	2205 13.00	0 13.00	2,010	0	0	0	0	2,010	3,110		550	550	029	.9 089	029		029	029 (029	029	2,020	3,120
9 2.	2211 21.70	0 21.70	3,150	0	0	0	0	3,150	5,000		006	950 1,	1,150 1,	1,150 1,200	00		1,040	1,040	1,040	1,030	3,500	5,350
10 22	2209 16.90	0 16.90	2,580	0	0	0	0	2,580	3,980		700	200	098	8 098	098	1,500	0 855	855	855	844	2,580	3,980
11 2	2210 12.30	0 12.30	1,860	0	0	0	0	1,860	2,860		200	200	620	620 6	620		635	5 635	635	655	1,860	2,860
Works 1	Works Expenditure	re	28,390	60,000	0	11,000	0	99,390	115,090	0	7,800 7	7,900 9,	9,470 35,	35,150 51,750	50 78,900	000'58 00	0 67,165	5 44,675	34,665	28,475	96,370	112,070
Operati	Operational Expenditure	nditure	4,000	4,000	4,000	0	0	12,000	20,000	2,000	2,500	3,500 3,	3,500 3,	3,800 3,700	000 4,000	0 4,000	0 4,000	4,000	4,500	4,500	11,000	19,000
Total Ex	Sotal Expenditure	e	32,390	64,000	4,000	11,000	0	111,390	135,090	2,000	10,300 11	11,400 12,	,970 38,	12,970 38,950 55,450		82,900 89,000	0 71,165	5 48,675	39,165 32,975	32,975	107,370	131,070
Total Ac	tual Qua	rterly Ex	Fotal Actual Quarterly Expenditure (Ush 000) to Date inc. this Quarter and Planned	(Ush 000	0) to Dat	e inc. this	, Quarte	r and Plan	nned	74	23,700		107	107,370		243,065	55		120,815		494,950	50
Cumula	tive Actu:	al Quarte	Cumulative Actual Quarterly Expenditure (Ush 000) to Date	diture (L	Jsh 000)	to Date				7	23,700		131,	131,070								
Actual I	unds Rec	eived by	Actual Funds Received by Quarter to Date (Ush 000)	o Date (I	Jsh 000)					7	25,000		115	115,000								
Cumula	tive Actus	d Funds	Cumulative Actual Funds Received by Quarter to Date (Ush 000)	by Quart	er to Da	te (Ush 0	(00)			7	25,000		140	140,000								
Balance	of Funds	Availabl	Balance of Funds Available at end this Quarter	his Quart	ter - (+) /	(-)				+	+ 1,300		+	8,930								

Date:

(CAO)

Signed:

(Sec. of Works)

Signed:

(DLGE)

Signed:

		Actual Works	Done to Date	(y)	10/A	9	10/C	0	10	0	0	10	0	10	6	10	6	10	10	10		108	9	0	A,C
	(s)	Actual Works	Done this Qr	(x)	V/9	9)/9	0	9	0	0	9	0	9	S	9	2	9	9	9	-	64	9	0	A,C
	Actual Interventions/Works to Date & Planned Next Quarter(s)	rter	June	(w)	1.50	0	0.75	0	2	0	0	0.50	3	2.80	1	0.50	1	2.70	06.0	0.50	-	13.15	2	0	0
	lext Q	Fourth Quarter	May	(v)	4	0	1	0	3	0	0	-	2	3	1.30	0.50	1	3	2	0.50		20.30	3	0	0
of FY	ned N	Four	Apr	(n)	4	0	2	0	3	0	3	1	0	4	2.5	0.50	1	3	2	0.50		23	0	3	0
arter (& Plai	ter	Mar	(t)	4	0	2	0	3	3	2	1	0	4	2.5	0.70	1	3	2	0.80		23.5	3	2	0
nd On	Date	Third Quarter	Feb	(s)	0/B	0	Q/D	3	0/E	3	0	0	0	0	0	9/0	0	0	H/0	0		0	3	3	Е, С, Н
Seco	orks to	Thir	Jan	(r)	0/B	4	Q/D	2	0	0	0	0	0	0/F	0	0	0	0	0	0		0	4	2	B,D,F
B) for	ons/Wo	rter	Dec	(b)	2/A	3	2/C	0	2	0	0	2	0	2	1	2	1	2	2	2		20	3	0	A,C
annal	rventic	Second Quarter	Nov	(d)	2	3	2	0	2	0	0	2	0	2	2	2	2	2	2	2		22	3	0	0
(Ref: Volume 3, Manual B) for Second Quarter of FY	ıl Inter	Secor	Oct	(0)	2	0	2	0	2	0	0	2	0	2	2	2	2	2	2	2		22	0	0	0
	Actua	ter	Sep	(u)	2	0	2	0	2	0	0	2	0	2	2	2	2	2	2	2		22	0	0	0
		First Quarter	Aug	(m)	2	0	2	0	2	0	0	2	0	2	2	2	2	2	2	2		22	0	0	0
		Firs	July	(1)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0
on Scheo	Jate	Total Planned	Works to Date	(k)	10/A	0	10/C	0	10	0	0	10	0	10	10	10	10	10	10	10		110	7	0	A,C
Works Implementation Schedule		Total Planned	Works this Qr	(j)	6/A	7	3/9	0	9	0	0	9	0	9	9	9	9	9	9	9		99	7	0	A,C
Impler	and to	Struc. Botnk	(ST)	(i)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	- km	- km	RH - km	/ ST
orks	uarter	🗸	(SR)	(h)	V	0	၁	0	0	0	0	0	0	0	0	0	0	0	0	0	A,C	RM	PM .	RH	SR/ST
>	ss this (Rehab. (RH)	(km)	(g)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
	ns/Worl		(km)	(f)	0	7	0	0	0	0	0	0	0	0	0	0	0	0	0	0	7				
	Planned Interventions/Works this Quarter and to Date		(RM)	(e)	9	0	9	0	9	0	0	9	0	9	9	9	9	9	9	9	99				
	ed Inte		Len. (km)	(p)	23.50	10.00	15.75	5.00	21.00	00.9	5.00	13.50	5.00	23.80	16.30	12.20	13.00	21.70	16.90	12.30					
	Plann		Len. (km)	(c)	23.50	23.50	20.75	20.75	26.00	26.00	26.00	13.50	13.50	23.80	16.30	12.20	13.00	21.70	16.90	12.30	pa				
District:			Link No.	(p)	2201	2201	2204	2204	2207	2207	2207	2208	2208	2202	2203	2206	2205	2211	2209	2210	Norks Planned				
Dist		Dist.		(a)	1	1	2	2	3	3	3	4	4	5	9	7	8	6	10	11	Vorks				

Notes: 1. Columns (a) to (d) are same as Form B1. Columns (e) to (k), also similar to Form B1, detail Planned Interventions/Works. Columns (l) to (w) detail Actual Works Done to date and Planned. 2. Details, including locations, of SR and ST Works are detailed in Form D2

(CAO) Signed: (Sec. of Works) Signed: (DLGE) Signed:

Date:

District:

- Reference Volume 3, Manual B Summary of Actual Expenditure (Ush 000) for SECOND Quarter of FY

ACTUAL						DIST		TOTAL ACTUAL	ACTUAL	TOTAL PAF	PAF	TOTAL	PROG
INTERVENTIONS/WORKS	PAF I	PAF II	PAF II PAF III DONOR	DONOR	DONOR	DEV	OTHER	EXPENDITURE	DITURE	EXPENDITURE	MITURE	PLANED	TO
DONE THIS QUARTER				Danida	USAID	FUND		SIHL	LO	THIS	LO	ANNUAL	DATE
- refer Forms B1 and B2								QUTR	DATE	QUTR	DATE	EXPEND	%
(A)	(B)	(C)	(D)	(E)	(F)	(G)	(H)	(I)	(J)	(K)	(L)	(M)	(N)
Routine Maint (RM) - 64 KM	28,770	0	0	0	0	0	0	28,770	44,470	28,770	44,470	83,200	54
Periodic Maint (PM) - 6 KM	0	96,600	0	0	0	0	0	26,600	26,600	26,600	26,600	183,750	31
Rehab (RH) - NIL	0	0	0	0	0	0	0	0	0	0	0	140,000	0
Road Botnk (SR) - A and C	0	0	0	0	11,000	0	0	11,000	11,000	0	0	11,000	100
Structure Botnk (ST) - NIL	0	0	0	0	0	0	0	0	0	0	0	33,000	0
Operational Expenses	3,500	3,800	3,700	0	0	0	0	11,000	19,000	11,000	19,000	44,000	43
TOTALS	32,270	60,400	3,700	0	11,000	0	0	107,370	131,070	96,370	120,070	494,950	2
QUARTERLY SUMMARY								Quarter	Cum.	Quarter	Cum.	Quarter	%
First Quarter	17,700	2,500	3,500	0	0	0	0	23,700	23,700	23,700	23,700	35,960	99
Second Quarter	32,270	60,400	3,700	0	11,000			107,370	131,070	96,370	120,070	106,960	112
Third Quarter												237,320	
Fourth Quarter												114,710	
TOTALS	49,970	62,900	7,200	0	11,000	0	0	131,070	131,070	120,070	120,070	494,950	24

Fund Request (Ush 000) for THIRD Quarter of FY

PLANNED INTERVENTIONS/WORKS -						DIST		TOTAL
NEXT QUARTER - refer Forms B1 and B2	PAF I	PAF II	PAF III	DONOR	DONOR	DEV	OTHER	PLANNED
				Danida	USAID	FUND		EXPENDITURE
(0)	(P)	0	(R)	(S)	(L)	<u>(</u>	(S	(W)
Routine Maint (RM) - 23.5 KM	599'6	0	0	0	0	0	0	699,6
Periodic Maint (PM) - 10 KM	0	83,400	0	0	0	0	0	83,400
Rehab (RH) - 7 KM	0	0	105,000	0	0	0	0	105,000
Road Botnk (SR) - NIL	0	0	0	0	0	0	0	0
Structure Botnk (ST) - Locations B,D,E,F,G and H	0	0	0	33,000	0	0	0	33,000
Operational Expenses - Procurement / contract supervision	4,000	4,000	4,000	0	0	0	0	12,000
Sub Totals	13,665	87,400	109,000	33,000	0	0	0	243,065
Balance Available - refer Form B1	2,000	3,000	3,930	0	0	0	0	
TOTAL FUND REQUEST NEXT QUARTER by SOURCE	11,665	84,400	105,070	33,000	0	0	0	

Date:

(CAO)

Signed:

(Sec. of Works)

Signed:

(DLGE)

Signed:

District: Worked Ex

Reporting Period: SECOND Quarter, FY /

Financial Progress to	Date (%)	54	65	100	0	48	0	100	0	54	0	0	0	53	0	54	0	54	54	0	54	99	54	0	53	
Cumulative Payments to		5,550,000	56,600,000	5,000,000	0	3,300,000	0	6,000,000	0	4,960,000	0	0	0	3,100,000	0	5,600,000	0	3,800,000	2,850,000	0	3,120,000	5,350,000	3,980,000	0	2,860,000	112,070,000
Contract Price	(Ush)	10,300,000	87,500,000	5,000,000	10,000,000	6,900,000	70,000,000	6,000,000	12,000,000	9,200,000	52,500,000	70,000,000	5,000,000	5,900,000	43,750,000	10,400,000	3,000,000	7,100,000	5,300,000	1,500,000	5,800,000	9,500,000	7,400,000	1,500,000	5,400,000	450,950,000
Physical Progress	to Date (%)	09	70	100	0	09	0	100	0	22				20		22		20	09		09	09	22		20	
	Worked (%)	55	65	100		22		100		22				22		55		22	22		22	22	22		22	
Actual Completion	Date			30/12/01				30/12/01																		
Scheduled Completion	Date	30/06/02	31/01/02	31/12/01		30/06/02		30/12/01		30/06/02				30/06/02		30/06/02		30/06/02	30/06/02		30/06/02	30/06/02	30/06/02		30/06/02	
Date Work Actually	Started	04/07/01	03/11/01	02/12/01		05/07/01		02/12/01		04/07/01				03/07/01		03/07/01		03/07/01	04/07/01		03/07/01	03/07/01	03/07/01		03/07/01	
Contract Duration	(weeks)	40	12	4	6	40	6	4	6	40				40		40	4	40	40		40	40	40		40	
Date Contract	Awarded	02/07/01	25/10/01	15/11/01	27/12/01	02/07/01	27/12/01	15/11/01	27/12/01	02/07/01				02/07/01		02/07/01	27/12/01	03/07/01	03/07/01		03/07/01	03/07/01	03/07/01		03/07/01	
Contract Price	(Nsh)	10,300,000	87,500,000	5,000,000	10,000,000	6,900,000	70,000,000	6,000,000	12,000,000	9,200,000	52,500,000	70,000,000	5,000,000	5,900,000	43,750,000	10,400,000	3,000,000	7,100,000	5,300,000	1,500,000	5,800,000	9,500,000	7,400,000	1,500,000	5,400,000	450,950,000
Engineers Estimate	(Nsh)	10,300,000	87,500,000	5,000,000	10,000,000	6,900,000	70,000,000	6,000,000	12,000,000	9,200,000	52,500,000	70,000,000	5,000,000	5,900,000	43,750,000	10,400,000	3,000,000	7,100,000	5,300,000	1,500,000	5,800,000	9,500,000	7,400,000	1,500,000	5,400,000	450,950,000 450,950,000
Workplan Estimate	(Nsh)	10,300,000	87,500,000	5,000,000	10,000,000	000,006,9	70,000,000	6,000,000	12,000,000	9,200,000	52,500,000	70,000,000	5,000,000	5,900,000	43,750,000	10,400,000	3,000,000	7,100,000	5,300,000	1,500,000	5,800,000	9,500,000	7,400,000	1,500,000	5,400,000	450,950,000
Contract Number Type of Works	Source of Funds	2201/01/0102/RM - PAF I	2201/02/0102/PM - PAF II	2201/03/0102/SR - Donor	2201/04/0102/ST - Donor	2204/01/0102/RM - PAF I	2204/02/0102/RH - PAF III	2204/03/0102/SR - PAF III	2204/04/0102/ST - Donor	2207/01/0102/RM - PAF I	2207/02/0102/PM - PAF II	2207/03/0102/RH - PAF III	2207/04/0102/ST - Donor	2208/01/0102/RM - PAF I	2208/02/0102/PM - PAF II	2202/01/0102/RM - PAF I	2202/02/0102/ST - Donor	2203/010102/RM - PAF I	2206/01/0102/RM - PAF I	2206/02/0102/ST - Donor	2205/01/0102/RM - PAF I	2211/01/0102/RM - PAF I	2209/01/0102/RM - PAF I	2209/02/0102/ST - Donor	2210/01/0102/RM - PAF I	

Total Commitments to Date Ush 450,950,000

Total Approved Annual Budget Ush 450,950,000

Remaining Available Balance 0sh

Reporting Period: SECOND Quarter, FY /

District: Worked Ex

Notes to the above Table -

- 1. Contract Number = District No and Road No/Contract No on that road for that year/Financial Year/Type of Works Source of Funds 2. Definitions of Types of Work; RM routine maintenance, PM periodic maintenance, RH rehabilitation, ST structures,
 - - SR spot repairs (inc. earthwork, minor structures and spot gravel), OT other detailed in Explanation/Comments below.

 3. Comments regarding Contract performance (refer Contract Ref. No in above Table)
 3.1 Fund releases have been timely and to the amounts requested.

Signed by DLGEngineer

Dated:

OFFICE OF THE CHIEF ADMINISTRATIVE OFFICER DISTRICT LOCAL GOVERNMENT P.O. BOX DISTRICT

	Date:

The Permanent Secretary Ministry of Works, Housing and Communications P O Box 10 Entebbe

ATTN: P.X.E. Eng Were Higenyi

Dear Sir,

Table A - Summary of Quarterly Progress Report - PAF

detailing planned activities and actual achievements during this reporting period.

	PLAN	NNED	ACHI	EVED	VARIATION	REASONS FOR
ACTIVITY	Target	Budget (a) (Ush 000)	Actual	Expend. (b) (Ush 000)	(a) - (b) (Ush 000)	VARIATIONS
Routine Mt	59 km	29,065	58 km	29,065	0	All activities included in
2. Periodic Mt	5 km	(43,750)	5 km	(43,750)	0	this FYs Work Plan have
3. Rehabilitation	3 km	15,000 (20,000)	3 km	15,000 (20,000)	0	been 100% completed
4. Road Bottlenecks	0	0	0	0	0	
5. Structural Bottlenecks	0	0	0	0	0	
6. Operational / Undistributed Exp.	Supervision activities	13,000	Procurement activities	13,000	0	
Bank charges	-	0	-	0	0	
Totals	Budget	57,065	Expend.	57,065	0	
	Balance at Er	nd Previous Qu	iarter	865		!
	Funds Receiv	ed This Quart	er	61,250		
	Balance Rem	aining		5,050		

Those activities planned but not undertaken during this Quarter are included in the plan for the subsequent Quarter(s) of this FY; refer Forms B1, B2, B3 and B4, attached hereto.

The list of all those roads on which works were performed during this reporting period follows; refer ADRICS Inventory data for official road names, and Form B2 of this Quarterly Progress Report -

Road	Road Name	Length Wor	ked On (km)	Type	of Wor	ks Done	(km)
No		Planned	Actual	RM	PM	RH	SR/ST
2201	mmm - (full official name as per Inventory)	9.55	9.55	9.55			
2204	kkk	3.75	3.75	3.75			
2207	000	11.00	11.00	8.00		3.00	
2208	uuu	7.50	7.50	2.50	5.00		
2202	ttt	9.80	9.80	9.80			
2203	ddd	4.80	4.80	4.80			
2206	SSS	1.50	1.50	1.50			
2205	eee	3.00	3.00	3.00			
2211	VVV	8.70	8.70	8.70			
2209	ууу	4.90	4.90	4.90			
2210	mmm	1.50	1.50	1.50			
	Totals (km)	66.00	66.00	58.00	5.00	3.00	

Table B below provides a cumulative summary of achievements against planned activities up to and including this reporting period; refer Annual District Road Work Plan for FY, and Forms B1, B2, B3 and B4 detailing planned activities and actual achievements during this and previous reporting periods.

Table B - Cumulative Summary of Quarterly Progress Report(s) - PAF

	PLAN	NED	ACHI	EVED	
ACTIVITY	Target	Budget	Actual	Expend.	COMMENTS
		(Ush 000)		(Ush 000)	
Routine Mt	189.95 km	83,200	189 km	83,200	PAF I
2. Periodic Mt	21 km	140,000	21 km	140,000	PAF II
		(43,750)		(43,750)	43,750 from USAID
3. Rehabilitation	10 km	120,000	10 km	120,000	PAF III
		(20,000)		(20,000)	20,000 from Danida
4. Road	A, C	(11,000)	A, C	(11,000)	Funding of 11,000 for these road bottlenecks
Bottlenecks					was provided by donor - USAID
5. Structural	B,D,E,F,G,H	(33,000)	B,D,E,F,G,H	(33,000)	33,000 from Danida
Bottlenecks					
6. Operational /	Procurement	44,000	Procurement	44,000	PAF
Undistributed Exp.	activities		activities		
Bank charges	-	0	-	0	
Totals	Budget	387,200	Expend.	387,200	
	Funds Receiv	red to Date		392,250	
	Un-spent Bal	ance Remainir	ng	5,050	
	Un-presented	Cheques		0	
	Balance on	Bank Staten	nent	5,050	- Copy of Bank Statement Attached

Table C below provides justification for the Release Request for the next quarter; refer Forms B1, B2 and B3

Table C - Quarterly Budget Request - All Funding Sources inc. PAF

ACTIVITY	PLAN FOR QUARTER	PAF I	PAF II	PAF	Other	TOTAL
				III		QUARTER
						(Ush 000)
1. Routine Maintenance	50 km	24,140	0	0	0	24,140
2. Periodic Maintenance	nil	0	0	0	0	0
3. Rehabilitation	nil	0	0	0	0	0
4. Road Bottlenecks	nil	0	0	0	0	0
5. Structural Bottlenecks	nil	0	0	0	0	0
6. Operational Expenses	Contract Doc's & Procurement	4,000	4,000	4,000	0	12,000
	Total Budget Requirement	28,140	4,000	4,000	0	36,140
	Un-spent Balance Remaining	5,050	0	0	0	5,050
	Release Request for Next Qurt	23,090	4,000	4,000	0	31,090

The following Attachments are included with this Quarterly Progress Report -

Note 1. If this is the First Quarterly Progress Report, then the following need to be Attachments -

- Forms D1, D2 and D3 detailing the Annual District Road Work Plan for the current FY these should have been provided with the Fourth Quarterly Progress Report of the previous FY; refer Note 3. below
- Form B1 Expenditure Schedule detailing actual spending during this Quarter and planned spending for the remainder of this FY
- Form B2 Works Implementation Schedule detailing actual works done this Quarter and planned for the remainder of this FY
- Form B3 Summary of Actual Expenditure during this Quarter together with the Fund Request for the following Quarter
- Form B4 Quarterly Progress Report detailing all district road works undertaken during this Quarter and planned for the remainder of this FY
- Bank Statement detailing all transactions during and to the end of this quarter

Note 2. If this is the Second and Third Quarterly Progress Reports, then the following need to be Attachments -

- Form B1 Expenditure Schedule detailing actual spending during this Quarter and planned spending for the remainder of this FY
- Form B2 Works Inplementation Schedule detailing actual works done this Quarter and planned for the remainder of this FY
- Form B3 Summary of Actual Expenditure during this Quarter together with the Fund Request for the following Quarter
- Form B4 Quarterly Progress Report detailing all district road works undertaken during this Quarter and planned for the remainder of this FY
- Bank Statement detailing all transactions during and to the end of this quarter

Note 3. If this is the Fourth Quarterly Progress Report, the list of Attachments will be as follows;

- Forms B1, B2, B3 and B4 for the last Quarter of the current FY including, in Form B3, the Fund Request for the following Quarter which will be the first quarter of the next FY
- Form D1 Annual District Road Work Plan for next FY, detailing the Expenditure Schedule for those works planned for implementation during the FY
- Form D2 Annual District Road Work Plan for the next FY, detailing the Works Implementation Schedule or programme for all those works planned during the FY
- Form D3 Annual District Road Work Plan for the next FY, detailing, for each of the works to be performed, the funding required, its source of origin, and the planned schedule for quarterly Fund Releases to ensure achievement of the works programme
- Bank Statement detailing all transactions during and to the end of this quarter

Yours sincerely,

Chief Administrative Officer

....Lira..... District Local Government

CC DLG Engineer,Lira....... District
LCV Chairman,Lira....... District
Sec. of Works,Lira....... District
Chairperson of the District Public Accounts Committee,
Chief Internal Auditor,

RDC, District

Director Budget, MFPED, Kampala

Donor Representative (s) - in all cases where donor funds are provided

)))))))			(())))))					
		Total Actual	Expend. to Date	(y)	25,300	87,500	24,900	70,000	14,200	52,500	70,000	5,900	43,750	13,400	7,100	6,800	5,800		8,900	5,400	450,950	44,000	494,950	494,950				
	r(s)	Total Actual	Expend. this Qr	(x)	3,580	0	2,700	0	3,180	0	35,000	2,100	43,750	3,600	2,475	1,850	2,010	3,110	2,555	1,905	107,815	13,000	120,815	494				
ı	uarte	rter	June	(w)	1,190		006		1,060			700	18,750	1,200	825	650	670	1,030	855	635	28,475	4,500	32,975					
_	Next Q	Fourth Quarter	May	(v)	1,190		006		1.060			700	25,000	1,200	825	009	029	1,040	855	635	34,665	4,500	48,675 39,165 32,975	120,815	494,950	125,000	200,000	6 050
	nned]	Four	Apr	(n)	1,190		006		1,060		35,000	700		1,200	825	009	029	1,040	855	635	44,675	4,000	48,675		4	1	w	+
	Actual Expenditure (Ush 000) to Date & Planned Next Quarter(s)	ter	Mar	(t)	1,180		006		1,060	22,500	35,000	700		1,200	825	009	029	1,040	855	635	67,165	4,000						
f FY	o Date	Third Quarter	Feb	(s)	5,000		7,000	35,000	5,000	30,000						1,500			1,500		85,000	4,000	82,900 89,000 71,165	243,065	374,135	235,000	375,000	270
rter of	000) t	Thir	Jan	(r)	5,000	30,900	5,000	35,000						3,000							18,900	4,000	82,900	7	3	2	8	
<u>h</u> Qua	(Ush	rter	Dec	(b)	6,300	31,000	6,700		1,070			200		1,200	800	630	029	1,200	098	620	51,750	3,700						
Fourt	nditure	Second Quarter	Nov	(d)	1,150	25,600	200		1,070			200		1,200	800	620	089	1,150	098	620	35,150	3,800	11,400 12,970 38,950 55,450	107,370	131,070	115,000	140,000	0 0 3 0
) for	Exper	Secon	Oct	(0)	1,100		200		1,070			200		1,200	800	009	029	1,150	098	620	9,470	3,500	: 076,21	-	1.	1	Ť	+
nual B	Actual	er	Sep	(n)	1,000		009		006			200		1,000	700	200	550	950	700	200	7,900	3,500	11,400					
3, Ma	ł	First Quarter	Aug	(m)	1,000		009		850			200		1,000	700	200	550	006	200	200	7,800	2,500		23,700	23,700	25,000	25,000	1 200
olume		First	July	(1)																	0	2,000	2,000 10,300	2	2	7	7	+
(Ref: Volume 3, Manual B) for Fourth Quarter of		Total Planned	Expend. to Date	(k)	25,300	87,500	24,900	70,000	14,200	52,500	70,000	5,900	43,750	13,400	7,100	6,800	5,800	9,500	8,900	5,400	450,950	44,000	494,950	peu				
dule	00)				,580	0	2,700	0	3,180	0	0				10	,850	2,010	3,110	29	5	7,815	0(S	Planned				
hed	6	T	Expeniture ((j)	3		7		3,		35,000	2,100	43,750	3,600	2,475	1,8	2,0	3,1	2,555	1,925	107,8	13,000	120,815					
ıre Sched	(Ush 0		Expe		0 3	0	0 2	0	0 3,	0	0 35,00	0 2,100	0 43,750	0 3,600	0 2,47;	0 1,8	0 2,0	0 3,1	0 2,55	0 1,92	0 107,8	0 13,0(0 120,81					
nditure Sched	Date (Ush 0	Struc. Botnk	(ST)	(j)	0 0	0 0				0 0	3;		4	3	2		. ,	.,	2	1	10.		120		ıte		sh 000)	
Expenditure Sched	and to Date (Ush 0)	Road Struc. Botnk Botnk			0	0	0 0	0 0	0 0	0	0 0 3.	0 0	0 0 4	0 0 3	0 0 2	0 0	0 0	0 0	0 0 2	0 0 1	0 0 10.	0 0	0 0 120) to Date	((ate (Ush 000)	
Expenditure Sched	uarter and to Date (Ush 0	Struc. Botnk	(ST)	(j)			0	0	0		0 3	0	0 4	ε 0	0 2	0	0	0	0 2	0 1	0 107	0	0 120		Ush 000) to Date	Ush 000)	ter to Date (Ush 000)	() / (†) ao
Expenditure Sched	this Quarter and to Date (Ush 00	Rehab. Road Struc. (RH) Botnk Botnk	(ST)	(h) (i)	0	0	0 0	0 0	0 0	0	0 0 3.	0 0	0 0 4	0 0 3	0 0 2	0 0	0 0	0 0	0 0 2	0 0 1	0 0 10.	0 0	0 0 120		diture (Ush 000) to Date	Date (Ush 000)	y Quarter to Date (Ush 000)	is Ougutou (+) / (-)
Expenditure Sched	enditure this Quarter and to Date (Ush 00	Rehab. Road Struc. (RH) Botnk Botnk	(SR) (ST)	(g) (h) (i)	0 0	0 0	0 0 0	0 0 0	0 0 0	0 0	35,000 0 0 3.	0 0 0	0 0 0 4.	ε 0 0 0	0 0 0 2	0 0 0		0 0 0 0	$\begin{bmatrix} 0 & 0 & 0 \end{bmatrix}$	I 0 0 0	35,000 0 0 107	4,500 0 0	39,500 0 0 120		y Expenditure (Ush 000) to Date	uarter to Date (Ush 000)	eceived by Quarter to Date (Ush 000)	of and this Quanta (+) / ()
Expenditure Sched	d Expenditure this Quarter and to Date (Ush 0	Routine Periodc Rehab. Road Struc. Maint. Maint (RH) Botnk Botnk	(RM) (PM) (SR) (ST)	(f) (g) (h) (i)	3,580 0 0 0	0 0 0	2,700 0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0	0 35,000 0 0 3	2,100 0 0 0 0	43,750 0 0 0 4	3,600 0 0 0 0 0 3	2,475 0 0 0 0 2	1,850 0 0 0 0 0	$\begin{bmatrix} 2,010 & 0 & 0 & 0 & 0 \end{bmatrix}$	$\begin{vmatrix} 3,110 & 0 & 0 & 0 & 0 \end{vmatrix}$	$\begin{vmatrix} 2,555 & 0 & 0 & 0 & 0 & 0 & 2 \end{vmatrix}$	1,905 0 0 0 0 500,1	43,750 35,000 0 0 107	4,000 4,500 4,500 0 0	48,250 39,500 0 0 120		uarterly Expenditure (Ush 000) to Date	d by Quarter to Date (Ush 000)	ands Received by Quarter to Date (Ush 000)	ilable at and this Quantan (+) / ()
Expenditure Sched	Tanned Expenditure this Quarter and to Date (Ush 0	Road Routine Periodc Rehab. Road Struc. Sect. Maint. Maint. (RH) Botnk Botnk	Len. (RM) (PM) (ST) (km) (km) (ST)	(e) (f) (g) (h) (i)	23.50 3,580 0 0 0	0 0 0 0	15.75 2,700 0 0 0 0	0 0 0 0 0	21.00 3,180 0 0 0 0	0 0 0 0 0009	5.00 0 0 35,000 0 0 3	13.50 2,100 0 0 0 0	5.00 0 43,750 0 0 0 4	23.80 3,600 0 0 0 0 3	16.30 2,475 0 0 0 0 2	12.20 1,850 0 0 0 0	$\begin{bmatrix} 13.00 & 2,010 & 0 & 0 & 0 & 0 \end{bmatrix}$	$\begin{bmatrix} 21.70 & 3,110 & 0 & 0 & 0 & 0 \end{bmatrix}$	16.90 2,555 0 0 0 0 2	12.30 1,905 0 0 0 0 0	29,065 43,750 35,000 0 0 10	4,000 4,500 4,500 0 0	33,065 48,250 39,500 0 0 120		stual Quarterly Expenditure (Ush 000) to Date	Received by Quarter to Date (Ush 000)	tual Funds Received by Quarter to Date (Ush 000)	As Ariallable at and this Orienton (1) / ()
District: Expenditure Sched	Planned Expenditure this Quarter and to Date (Ush 000	Total Road Routine Periodc Rehab. Road Struc. Road Sect. Maint. Maint. (RH) Botnk Botnk	(RM) (PM) (SR) (ST)	(d) (e) (f) (g) (h) (i)	3,580 0 0 0	0 0 0	2,700 0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0 0	0 0 35,000 0 3	2,100 0 0 0 0	0 43,750 0 0 0 4	3,600 0 0 0 0 0 3	2,475 0 0 0 0 2	1,850 0 0 0 0 0	$\begin{bmatrix} 2,010 & 0 & 0 & 0 & 0 \end{bmatrix}$	$\begin{vmatrix} 21.70 & 3,110 & 0 & 0 & 0 & 0 \end{vmatrix}$	$\begin{vmatrix} 2,555 & 0 & 0 & 0 & 0 & 0 & 2 \end{vmatrix}$	1,905 0 0 0 0 500,1	43,750 35,000 0 0 107	4,500 4,500 0 0	48,250 39,500 0 0 120	otal Actual Quarterly Expenditure (Ush 000) to Date inc. this Quarter and Pl	umulative Actual Quarterly Expenditure (Ush 000) to Date	ctual Funds Received by Quarter to Date (Ush 000)	umulative Actual Funds Received by Quarter to Date (Ush 000)	of Unnder Arreitable of and this Quantum (+) ()

Date:

(CAO)

Signed:

(Sec. of Works)

Signed:

(DLGE)

Signed:

		Actual Works	Done to Date	(y)	23.50	10.00	15.70	5.00	21.00	0.09	5.00	13.50	5.00	23.80	16.30	12.00	13.00	21.70	16.50	12.00		189	21	10	all
	(s)	Actual Works	Done this Qr	(x)	9.55	0	3.75	0	8.00	0	3.00	2.50	5.00	9.80	4.80	1.50	3.00	8.70	4.90	1.50	-	28	S	3	0
	uarter	rter	June	(w)	1.55	0	0.70	0	2	0	0	0.50	3	2.80	1	0.50	1	2.70	06.0	0.50	-	14.20	2	0	0
	lext Q	Fourth Quarter	May	(v)	4	0	1	0	3	0	0	-	2	3	1.30	0.50	-	3	2	0.50	i	20.30	3	0	0
f FY	uned N	Four	Apr	(n)	4	0	2	0	3	0	3	1	0	4	2.50	0.50	1	3	2	0.50	i	23.50	0	3	0
arter 0	& Pla	rter	Mar	(t)	4	0	2	0	3	3	2	1	0	4	2.50	0.70	1	3	2	08.0	-	24	3	2	0
<u>th</u> Qu	Date Date	Third Quarter	Feb	(s)	0/B	0	0/D	3	0/E	3	0	0	0	0	0	9/0	0	0	H/0	0		0	3	3	Е,G,Н
Four	orks to	Thir	Jan	(r)	0/B	4	0/D	2	0	0	0	0	0	0/F	0	0	0	0	0	0		0	4	2	B,D,F
(Ref: Volume 3, Manual B) for Fourth Quarter of FY	Actual Interventions/Works to Date & Planned Next Quarter(s)	ırter	Dec	(b)	2/A	3	2/C	0	2	0	0	2	0	2	1	2	1	2	2	2		20	3	0	A,C
annal	rventi	Second Quarter	Nov	(d)	2	3	2	0	2	0	0	2	0	2	2	2	2	2	2	2		22	3	0	0
ie 3, M	al Inte	Seco	Oct	(0)	2	0	2	0	2	0	0	2	0	2	2	2	2	2	2	2		22	0	0	0
Volum	Actua	ter	Sep	(u)	2	0	2	0	2	0	0	2	0	2	2	2	2	2	2	2		22	0	0	0
(Ref:		First Quarter	Aug	(m)	2	0	2	0	2	0	0	2	0	2	2	2	2	2	2	2		22	0	0	0
		Firs	July	(1)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0
ntation Schedule		Total Planned	Works to Date	(k)	23.50	10.00	15.70	5.00	21.00	6.00	5.00	13.50	5.00	23.80	16.30	12.00	13.00	21.70	16.50	12.00		189	21	10	all
nentati	Date	Total Planned	Works this Qr	(j)	9.55	0	3.75	0	8.00	0	3.00	2.50	5.00	08.6	4.80	1.50	3.00	8.70	4.90	1.50	-	89	S	3	0
Works Impleme	and to	Struc. Botnk	(ST)	(i)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	- km	- km	- km	SR / ST
orks /	uarter	Road Botnk	(SR)	(h)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	RM	PM	RH	SR
	ks this Q	Rehab. (RH)	(km)	(g)	0	0	0	0	0	0	3.00	0	0	0	0	0	0	0	0	0	3				
	ns/Wor		(PM) (km)	(f)	0	0	0	0	0	0	0	0	5.00	0	0	0	0	0	0	0	S				
	Planned Interventions/Works this Quarter and to Da	Routine Periodc Maint. Maint.	(RM)	(e)	9.55	0	3.75	0	8.00	0	0	2.50	0	08.6	4.80	1.50	3.00	8.70	4.90	1.50	85				
	ed Int		Len. (km)	(p)	23.50	10.00	15.75	5.00	21.00	00.9	5.00	13.50	5.00	23.80	16.30	12.20	13.00	21.70	16.90	12.30					
	Plann	Total Road	Len. (km)	(c)	23.50	23.50	20.75	20.75	26.00	26.00	26.00	13.50	13.50	23.80	16.30	12.20	13.00	21.70	16.90	12.30	pa				
District:		Dist. Road	Link No.	(p)	2201	2201	2204	2204	2207	2207	2207	2208	2208	2202	2203	2206	2205	2211	2209	2210	Works Planned				
Dist		Dist.		(a)	1	_	2	7	3	3	3	4	4	5	9	7	∞	6	10	11	Works				

Notes: 1. Columns (a) to (d) are same as Form B1. Columns (e) to (k), also similar to Form B1, detail Planned Interventions/Works. Columns (l) to (w) detail Actual Works Done to date and Planned. 2. Details, including locations, of SR and ST Works are detailed in Form D2

Date: (CAO) Signed: (Sec. of Works) Signed: (DLGE) Signed:

District:

- Reference Volume 3. Manual B Summary of Actual Expenditure (Ush 000) for Fourth Quarter of FY

Saminally of Actual Expendicular (Can 000) for Fourth Qual to 1 1		dvi in	· III III I		101 (000		1 Teny	1 1 IN 1'	_	NOTO LOTO	- Incipitation Volume 3, intainal D	Maildal D	
ACTUAL						LSIQ		TOTAL ACTUAI	ACTUAL	TOTAL PAF	, PAF	TOTAL	PROG
INTERVENTIONS/WORKS	PAF I	PAF II	PAF III DONOR	DONOR	DONOR	DEV	OTHER	EXPENDITURE	NTURE	EXPENDITURE	NTURE	PLANED	TO
DONE THIS QUARTER				Danida	USAID	FUND		THIS	TO	THIS	LO	ANNUAL	DATE
- refer Forms B1 and B2								QUTR	DATE	QUTR	DATE	EXPEND	%
(A)	(B)	(C)	(D)	(E)	(F)	(G)	(H)	(I)	(J)	(K)	(L)	(M)	(N)
Routine Maint (RM) - 58 KM	29,065	0	0	0	0	0	0	29,065	83,200	29,065	83,200	83,200	100
Periodic Maint (PM) - 5 KM	0	0	0	0	43,750	0	0	43,750	183,750	0	140,000	183,750	100
Rehab (RH) - 3 KM	0	0	15,000	20,000	0	0	0	35,000	140,000	15,000	120,000	140,000	100
Road Botnk (SR) - NIL	0	0	0	0	0	0	0	0	11,000	0	0	11,000	100
Structure Botnk (ST) - NIL	0	0	0	0	0	0	0	0	33,000	0	0	33,000	100
Operational Expenses	4,000	4,500	4,500	0	0	0	0	13,000	44,000	13,000	44,000	44,000	100
TOTALS	33,065	4,500	19,500	20,000	43,750	0	0	120,815	494,950	57,065	387,200	494,950	100
QUARTERLY SUMMARY								Quarter	Cum.	Quarter	Cum.	Quarter	%
First Quarter	17,700	2,500	3,500	0	0	0	0	23,700	23,700	23,700	23,700	35,960	99
Second Quarter	32,270	60,400	3,700	0	11,000	0	0	107,370	131,070	96,370	120,070	106,960	100
Third Quarter	10,835	90,550	108,680	33,000	0	0	0	243,065	374,135	210,065	330,135	237,320	102
Fourth Quarter	33,065	4,500	19,500	20,000	43,750	0	0	120,815	494,950	57,065	387,200	114,710	105
TOTALS	93,870	157,950	135,380	53,000	54,750	0	0	494,950	494,950	387,200	387,200	494,950	100

FY
(NEXT)
of (
Juarter
_
First
\mathbf{for}
Ush 000)
(Ush
guest
Red
Fund I
. 1

PLANNED INTERVENTIONS/WORKS -						DIST		TOTAL
NEXT QUARTER - refer Forms B1 and B2	PAF I	PAF II	PAF III	DONOR	DONOR	DEV	OTHER	PLANNED
				Danida	USAID	FUND		EXPENDITURE
(0)	(P)	0	(R)	(S)	(T)	9	(3)	(W)
Routine Maint (RM) - 50 KM	24,140	0	0	0	0	0	0	24,140
Periodic Maint (PM) - NIL	0	0	0	0	0	0	0	0
Rehab (RH) - NIL	0	0	0	0	0	0	0	0
Road Botnk (SR) - NIL	0	0	0	0	0	0	0	0
Structure Botnk (ST) - NIL	0	0	0	0	0	0	0	0
Operational Expenses - Contract Doc's / Procurement	4,000	4,000	4,000	0	0	0	0	12,000
Sub Totals	28,140	4,000	4,000	0	0	0	0	36,140
Balance Available - refer Form B1	5,050	0	0	0	0	0	0	
TOTAL FUND REQUEST NEXT QUARTER by SOURCE	23,090	4,000	4,000	0	0	0	0	

Date:

(CAO)

Signed:

(Sec. of Works)

Signed:

(DLGE)

Signed:

District:

Reporting Period: Fourth Quarter, FY /

_																									
Financial Progress to Date (%)	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
Cumulative Payments to Date (Ush)	10,300,000	87,500,000	5,000,000	10,000,000	6,900,000	70,000,000	6,000,000	12,000,000	9,200,000	52,500,000	70,000,000	5,000,000	5,900,000	43,750,000	10,400,000	3,000,000	7,100,000	5,300,000	1,500,000	5,800,000	9,500,000	7,400,000	1,500,000	5,400,000	450,950,000
Current Contract Price (Ush)	10,300,000	87,500,000	5,000,000	10,000,000	6,900,000	70,000,000	6,000,000	12,000,000	9,200,000	52,500,000	70,000,000	5,000,000	5,900,000	43,750,000	10,400,000	3,000,000	7,100,000	5,300,000	1,500,000	5,800,000	9,500,000	7,400,000	1,500,000	5,400,000	450,950,000
Physical Progress to Date (%)	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
Contract Time Worked (%)	100	125	100	110	100	100	100	145	100	135	100	135	100	100	100	150	100	100	100	100	100	100	150	100	
Actual Completion Date	30/06/02	26/02/02	30/12/01	31/03/03	30/06/02	23/03/02	30/12/01	23/04/02	30/06/02	30/04/02	15/04/02	15/03/02	30/06/02	16/06/02	30/06/02	14/02/02	30/06/02	30/06/02	15/02/02	30/06/02	30/06/02	30/06/02	22/02/02	30/06/02	
Scheduled Completion Date	30/06/02	31/01/02	31/12/01	23/03/02	30/06/02	23/03/02	30/12/01	23/03/02	30/06/02	12/04/02	15/04/02	07/03/02	30/06/02	16/06/02	30/06/02	29/01/02	30/06/02	30/06/02	15/02/02	30/06/02	30/06/02	30/06/02	12/02/02	30/06/02	
Date Work Actually Started	04/07/01	03/11/01	02/12/01	13/01/02	05/07/01	13/01/02	02/12/01	13/01/02	04/07/01	12/02/02	02/03/02	02/02/02	03/07/01	15/04/02	03/07/01	02/01/02	03/07/01	04/07/01	21/01/02	03/07/01	03/07/01	03/07/01	15/01/02	03/07/01	
Contract Duration (weeks)	40	12	4	6	40	6	4	6	40	6	8	3	40	8	40	4	40	40	4	40	40	40	4	40	
Date Contract Awarded	02/07/01	25/10/01	15/11/01	27/12/01	02/07/01	27/12/01	15/11/01	27/12/01	02/07/01	02/02/02	15/02/02	15/02/02	02/07/01	15/04/02	02/07/01	27/12/01	03/07/01	03/07/01	15/01/02	03/07/01	03/07/01	03/07/01	12/01/02	03/07/01	
Contract Price (Ush)	10,300,000	87,500,000	5,000,000	10,000,000	6,900,000	70,000,000	6,000,000	12,000,000	9,200,000	52,500,000	70,000,000	5,000,000	5,900,000	43,750,000	10,400,000	3,000,000	7,100,000	5,300,000	1,500,000	5,800,000	9,500,000	7,400,000	1,500,000	5,400,000	450,950,000
Engineers Estimate (Ush)	10,300,000	87,500,000	5,000,000	10,000,000	6,900,000	70,000,000	6,000,000	12,000,000	9,200,000	52,500,000	70,000,000	5,000,000	5,900,000	43,750,000	10,400,000	3,000,000	7,100,000	5,300,000	1,500,000	5,800,000	9,500,000	7,400,000	1,500,000	5,400,000	450,950,000
Workplan Estimate (Ush)	10,300,000	87,500,000	5,000,000	10,000,000	6,900,000	70,000,000	6,000,000	12,000,000	9,200,000	52,500,000	70,000,000	5,000,000	5,900,000	43,750,000	10,400,000	3,000,000	7,100,000	5,300,000	1,500,000	5,800,000	9,500,000	7,400,000	1,500,000	5,400,000	450,950,000
Contract Number Type of Works Source of Funds	2201/01/0102/RM - PAF I	2201/02/0102/PM - PAF II	2201/03/0102/SR - Donor	2201/04/0102/ST - Donor	2204/01/0102/RM - PAF I	2204/02/0102/RH - PAF III	2204/03/0102/SR - PAF III	2204/04/0102/ST - Donor	2207/01/0102/RM - PAF I	2207/02/0102/PM - PAF II	2207/03/0102/RH - PAF III	2207/04/0102/ST - Donor	2208/01/0102/RM - PAF I	2208/02/0102/PM - PAF II	2202/01/0102/RM - PAF I	2202/02/0102/ST - Donor	2203/010102/RM - PAF I	2206/01/0102/RM - PAF I	2206/02/0102/ST - Donor	2205/01/0102/RM - PAF I	2211/01/0102/RM - PAF I	2209/01/0102/RM - PAF I	2209/02/0102/ST - Donor	2210/01/0102/RM - PAF I	

450,950,000	450,950,000	0
Ush	Ush	Ush
Total Commitments to Date	Total Approved Annual Budget	Remaining Available Balance

District:

Reporting Period: Fourth Quarter, FY /

Notes to the above Table
1. Contract Number = District No and Road No/Contract No on that road for that year/Financial Year/Type of Works - Source of Funds

2. Definitions of Types of Work; RM - routine maintenance, PM - periodic maintenance, RH - rehabilitation, ST - structures,

SR - spot repairs (inc. earthwork, minor structures and spot gravel), OT - other detailed in Explanation/Comments below.

3. Comments regarding Contract performance (refer Contract Ref. No in above Table)
All contracts 100% complete.

Signed by DLGEngineer

Dated:

Annex 4

Users Manual - Quarterly Progress Reporting System (QPRS)



Ministry of Works, Housing and Communications

Quarterly Progress Reporting System (QPRS)





Users Manual

TABLE OF CONTENTS

1. Introduction	l	1
2. Installation	of QPRS/ RAMPS Applications	3
3. Starting the	Program	9
4. Setup List of	of Works in the ADRWP	12
5. Schedule of	f Works and Expenditures in ADRWP	16
6. ADRWP – E	Budget Summary	19
7. Actual Work	ks & Expenditure + Planned Next Quarters	20
8. QPR – Sum	nmary of Expenditure and Next Quarter's Budget	24
9. Data Expor	t – Import Operation	29
10. Lookup Ta	ables of RAMPS in QPRS	30
11. Reports in	QPRS	32
APPENDICE	S	
Appendix-A	E-R Diagram of QPRS (MS Access format)	
Appendix-B	Trouble Shooting	
Appendix-C	Sample Reports of QPRS	

1. Introduction

Quarterly Progress Reporting System (QPRS) is an application module of the Rehabilitation and Maintenance Management System (RAMPS). QPRS is used to manage, analyse generate reports related to the progress of implementation of District and Community Access Road Network development works. It is designed to assist both the District Engineer and the Ministry of Works, Housing and Communications to monitor the implementation of road works in terms of time management, quality, accountability and overall efficiency. Similar to the primary module of RAMPS, all data of QRRS are fed at the district level and the Ministry at Entebbe receives a district from each district containing the quarterly progress data at the end of each quarter. The MoWHC uses the RAMPS-HQ module to download and compile the data into the central with the possibility of enormous analysis of the data. A printed set of reports of QPRS is also sent to the Ministry of Finance and thus QPRS also assists them to follow the recommendation by the MoWHC and to streamline the release of fund to different districts, as they would probably get all the data from the districts relevant to release of fund.

The process of QPRS starts with working out and entering the Annual District Road Work Plan (ADRWP) at the district. When the District Engineer starts detail of ADRWP, s/he already knows the budget ceiling for the district from different funding sources for different category of works (viz. routine maintenance, periodic maintenance etc.). Once the ADRICS was done, the District Engineer also knows how much money s/he needs for to maintain and rehabilitate the whole network in the district and the priority ranking of the network. Based on the RAMPS primary network priority and the availability of funds, the District Engineer then breaks the total network to be developed in the financial year in a number of pieces which eventually forms an individual "Work" in the ADRWP. How the district Engineer divides the network into pieces depends on the geographical location, nature of works and possible source of funding, capacity of the contractor to handle a work, capacity of the District Engineers office (in terms of supervising staff and the equipment) and more importantly the experience from the previous years.

Even though ADRICS is not completed in a FY, RAMPS will still allow the District Engineer to carry out QPRS with limited reports. However, preparation of ADRWP with chainage reference and the numbering reference of the respective road is a must. Once the ADRWP is prepared at the beginning of fiscal year, and monthly scheduled is done, it is followed for the rest of the FY. At the end of each quarter, the ADRWP is adjusted for the remaining quarter such a way that any incomplete work is pushed towards the following quarter and vice versa. It may so happen that a new work is undertaken in the middle of the fiscal year

and other work is needed to drop from the list. The QPRS module does not stop the District Engineer to make such change; however, the RAMPS-HQ module will detect and if such change have been made. In any case, it is always suggested to avoid any change in the ADRWP in the middle of the FY, because, the whole purpose is to prepare and follow a time frame in order to bring efficiency in the contract administration and keep on changing the ADRWP will jeopardize such objective.

2. Installation of QPRS/ RAMPS Applications

The current version of Rehabilitation and Maintenance Planning System (RAMPS, version 1.1, March 2003) comprises of three modules namely a) RAMPS primary module b) Quarterly Progress Reporting System module and c) Personnel & Equipment Database Module. All these three modules are now incorporated in one installation CD and the base program used for all of them is Access XP (i.e. version 10/ 2002). That means the base program of the previous version of RAMPS, which was Access 97 has also been upgraded, however, no additional features has been built into it. All other module in the system is related to and based on the primary module of RAMPS and thus if you would like to use the QPRS, it is required that the RAMPS primary module version 1.1 is installed in your machine before. If any previous version of RAMPS existing in your machine, it is suggested to uninstall it before installing the current version of RAMPS, however, do not delete the RAMPS directory - because it will delete your existing data. Follow the manual of previous version of RAMPS to see how to uninstall that version of RAMPS from your machine. Installation of this version of RAMPS will not affect any existing data in your machine, nevertheless, it is also suggested to export the data into a file and save it in a safe location along with the back-end data file of RAMPS (i.e. C:\RAMPS\Ramps_be.mdb). If you loose any data (for any other reason apart from installation of RAMPS Applications version 1.1), copy the back-end data file from your backup to get back the data. In this connection, it is suggested to backup the RAMPS data in safe location at regular basis.

The installation CD of Rehabilitation and Maintenance Planning System consists of an autorun batch file which activates as soon as you insert the CD into the drive. The batch-file interface for the installation program is shown in figure-1. Some machine may not trigger the auto-run batch file if its CD-drive property is configured such way. To way to access CD drive property varies from one operating system to other and it is suggested to take assistance from any available system support personnel to do change such property. However, for the purpose of installation of RAMPS, if the CD auto-run function is not triggered, browse the CD and click on the "BatchSetup.exe" file to open the RAMPS installation batch-file interface. In case of any problem with installation, please refer to the troubleshooting section of installation at the end of this manual.

The primary module of RAMPS requires all together 100 MB of free space in your hard disk along with the Access Runtime (MS Access XP or 2000 is already installed in your machine, it may take less space). The space required for QPRS and other additional module is approximately 25MB for each. However, it is recommended to keep enough space (at least

100 MB) in your hard disk to run the program efficiently. The minimum RAM required for RAMPS is 64 MB.

Before starting the installation make sure that all other program in your machine are closed. The batch-file interface comprises of six buttons and the use of those buttons is described as follows:




Figure-1: Start-up window of RAMPS Applications installation



The first step of installation process is to install Microsoft Access XP (i.e. version 10 / 2002) in your machine and use "Install ART" button to do so. If the Access 2002 Runtime was installed previously, there is no need to install it second time and this step can be skipped. If the installation

program finds Access Runtime, it will proceed to the Maintenance mode of Access Runtime (figure-3). Repair/ Maintenance of Access is not needed unless the program is corrupted and such message comes up during the use of RAMPS Applications. Now in case of fresh installation or Access Runtime, the program asks for default directory location of Access and usually a location name given by default is C:\Porgram Files\Microsoft Office. Change the directory to "C:\Program Files\Access Runtime" (see figure-2), other-wise there is possibility of conflict with other version of Microsoft Access installed in your machine. Remember to install Access Runtime before installing any of the RAMPS module, as those modules will create a shortcut in the Windows Program Start-up Menu with a reference to

the location of the MSAccess.EXE of Access Runtime. Once you have started, the program itself will guide throughout to install Access Runtime.




Figure-2: Instillation of MS Access XP Runtime




Figure-3: Maintenance Mode of MS Access Runtime installation



The installation of RAMPS starts by pressing "Install RAMPS" button of SetupBatch program (figure-1). The SetupBatch program first search if there is any existing RAMPS_be.mdb file under C:\RAMPS folder of your hard disk. If it find such file, it keep the file, otherwise, it copies an empty

Ramps be.mdb file into that location. The program also copies another empty file called Ramps be ori.mdb regardless it finds any data file under C:\RAMPS folder. The purpose of the second empty data file is to replace the existing data file (ramps be.mdb) if that file is corrupted for any reason. After searching and copying the ramps_be.mdb file, the Setupbatch.exe program then calls the Setup.exe program of RAMPS, which is located under \Setup RAMPS\Setup.exe location of the installation CD. As this setup program runs. you are prompted with a screen as show in figure-3 with the possibility to change default directory. Keep the Directory as C:\RAMPS as per default prompt and press the button with computer icon to continue installation. In fact all the modules of RAMPS are now located under the same folder called C:\RAMPS. Even if you change the default folder to any other location, still the program will be installed and run and it will put the front end interface file (i.e. RAMPS XP.mde) and back-end data files at separate locations. Please remember that as the front-end interface file is run with RAMPS, it establish its link to back-end file, movie clip etc under the fixed location, which is always c:\RAMPS. So no matter where you put the front-end file, RAMPS installation program will put the fixed location files (viz. ramps be.mdb, rampsLUT.mdb etc.) under C:\RAMPS folder.




Figure-3: Installation button and Default Directory of RAMPS

RAMPS installation program put a shortcut under the Windows Program Startup menu with the name "RAMPS Application". The target property of the shortcut is as follows:

"C:\Program Files\Access Runtime\Office10\Msaccess.exe" "C:\RAMPS\RAMPS_XP.mde"

The default icon for the shortcut is Eisbldr, which is also located under C:\RAMPS folder.

For any reason if the shortcut is deleted or lost, from the Startup menu, you can create your own shortcut using the target property as described above. Now to put the shortcut on your Desktop follow the following steps:

- a) Put cursor on the Start Menu Program group called "RAMPS Application"
- b) Press right button of mouse
- c) Select the popup menu command "Send To" ▶ "Desktop (Create shortcut)"




Figure-4: Creating Shortcut on Windows Desktop



The installation of QPRS starts by pressing "Install QPRS" button of SetupBatch program (figure-1). The SetupBatch program first search if there is any existing QPRS_be.mdb file under C:\RAMPS folder of your hard disk. If it find such file, and if the date of last modification is newer than 1/1/2003 only then it keeps it; otherwise, it copies an empty

QPRS_be.mdb file into that location, even through overwriting. The program also copies another empty file called QPRS_be_ori.mdb regardless it finds any data file under C:\RAMPS folder. After searching and copying the ramps_be.mdb file, the Setupbatch.exe program then calls the Setup.exe program of QPRS, which is located under \Setup QPRS\Setup.exe location of the installation CD. As this setup program runs, a Prompt Window similar to figure-3 popup with the possibility to change default directory. Keep the Directory as C:\RAMPS as per default prompt and press the button with computer icon to continue installation. As mentioned before, all modules of RAMPS are now located under the same folder called C:\RAMPS.

QPRS installation program put a shortcut under the Windows Program Startup menu with the name "QPRS Version 1.0" (although current version is 1.1, the shortcut name has not been changed, so that the new program overwrites the previous shortcut. The target property of the shortcut is as follows:

[&]quot;C:\Program Files\Access Runtime\Office10\Msaccess.exe" "C:\RAMPS\QPRS XP.mde"



Installation of "Personnel and Equipment Database" is similar to installation of RAMPS and QPRS. Here once again to mention that the folder location for the program should be the default location called C:\RAMPS. After installation of the program is finished, you can also create a shortcut on the

Desktop following the procedure described before for RAMPS and QPRS modules. The target property of the shortcut in the Windows Start Menu is as follows:

"C:\Program Files\Access Runtime\Office10\Msaccess.exe" "C:\RAMPS\ EmpEquip_XP.mde"



Installation of "Windows Component Update" is an additional program, which is needed to install at some special circumstance such as MS Access Runtime is not running properly in your machine. Usually all the Windows library files (located under **Windows\System** folder) required by Access Runtime (version 10) come with the Window Operating System itself.

However, for any reason, if such files are not installed in your machine, RAMPS program still opens but it does not work and gives the message "can not create Active-X object" or other similar messages. In other case, the start-up movie clip may not work. In all such cases, install the Windows Component update. As started the installation program guides thought the installation process. Now if the Competent files are already installed in your computer, running the "Win Comp Update" will try to remove the existing files from your machine (see figure-3). So do not use the "Component Update Setup" unless it is needed.




Figure-5: System Files Update prompted for uninstalling

3. Starting the Program

Once the QPRS is installed in the machine, a shortcut titled "QPRS Application ver 1.0" is created under "RAMPS Application" folder of Windows Program Start Menu. Either use this shortcut or use copy of the shortcut on the Desktop (figure-6) to start the QPRS program. As the QPRS program is opened, a startup movie clip is played in on screen. Press Esc button to stop the movie clip. As the movie clip is stopped, the password entry box is enabled and the cursor moves into the box. Default password for QPRS is "lira", all in small letter. However, you can later on change the password to any other alpha-numeric string of your own using the "change password" command button. As you enter the correct password, all



Figure-6: Shortcut icon on desktop to start QPRS

the buttons in the in the screen is enabled and you get a screen similar to as shown in figure-8, which is called "Main Switchboard" of the program.



Figure-7: Start-up Window of QPRS with movie clip

The start-up movie clip is inserted in QPRS through the Active-X control of Windows Media Player coming with Windows OS. Sometimes some other program also installs the Active-X control in the machine, which may conflict with the Media Player of MS Access. In such case the start-up movie may not work and gives the message "OLE automation error". As the start-up movie clip built in the Main Switchboard of the software, the error in the media clip may stop activation of the Switchboard button. There are certain ways how you can correct the problem, and the easiest one is to de-activate the movie clip from the main switchboard, and the procedure has been discussed later in the trouble shooting section of this manual.




Figure-8: Start-up Switchboard of QPRS module

There are nine buttons in the start-up switchboard (figure-8) and each button represents a specific function in the program. List of the buttons in the switchboard and their functions described briefly in table-1 as follows.

Table-1: List of buttons in start-up switchboard and their functions

Button Title	Function
Setup List of Works in the ADRWP	Use this button to define a list of activities to be
	undertaken in a particular financial year. The list
	of the activities thus defined comprises the
	ADRWP. Each row in the list is then treated as a
	separate contract.
Enter Impl. & Expenditure Schedule for ADRWP	Use this button to define monthly schedule of
	each of the activity (i.e. work) in the ADRWP
	work list. Once the work list is schedule over the
	month, monthly expenditure corresponding to
	each month's work is also calculated based on
	the predefined unit rates. Now the actual
	monthly expenditure (i.e. money paid to the
	contractor) for each contract is obviously
	different than the corresponding works
	performed for the work. Because, in case of
	contract work, the measurement may not be
	taken on monthly basis, and also the full amount
	of money for the amount of work performed may
	not be available with the district and so on.

Button Title	Function
	However, the calculation of monthly expenditure will help to assess the amount of money needed in the respective quarter.
Summary of Expenditure Schedule for ADRWP	Each work listed in the ADRWP corresponds to a particular source of funding (viz. PAF-1). Based on the expenditure schedule prepared under form-D1, the amount of expenditure scheduled in each quarter against various funding sources are summarized under this function. Another purpose of this button is to enter quarterly operational expenditure planned in various quarter against different funding sources.
Lookup Tables + Unit Rates	This button is primarily used to set the Unit Cost of Works in the System. The list of item of works is the same as that of RAMPS, however, you need to enter a separate set of Unit Cost in the QPRS module in addition to that of main module of RAMPS.
Quarterly Progress and Next Quarter's Plan	Use this button to record actual work done in the quarter and actual payment made during the quarter against individual "Works" in the ADRW. The actual work done in each month should now correspond to the measurement taken in the field and the expenditure should correspond to actual payment made to the contractor.
Summary of progress in the quarter	As understood from its name, this button obviously summarizes the amount of expenditure done in the respective quarter against individual quarter. Apart from that, use this button to enter amount of operational expenditure made in the quarter. Another purpose of this button is to enter the amount of fund received in the quarter and to calculate and adjust the amount of fund to be requested to the Ministry for the following quarter.

Button Title	Function
	Use this button to print various reports in the
	system. Similar to the primary module of
	RAMPS, there are a number of "data filtering"
	tables in the form, which can be used to retrieve
	report with data fulfilling specific criteria.
Data Export/ Import	One of the important functions of Quarterly
	Progress Reporting System is to send the
	ADRWP and quarterly progress of road works to
	the Ministry at the end of every quarter. QPRS
	module enables the District Engineer to send
	the data in floppy diskette media along with the
	signed printed versions of the relevant reports.
	The digital copy of the report enables the
	Ministry to avoid a lot of data entering at the
	their office whereas they have an enormous
	possibility to analyse the data compiled at the
	district. The function for exchanging data
	between the Ministry and the districts is
	performed by this button.

4. Setup List of Works in the ADRWP

As the program is opened for the first time, there is no data in it and the default district is set to Lira. Now if you want to add any data into the program, it will go under the Lira district. So the first step in the program is to change the default district and the fiscal year. Those entries are found under the "Setup List of Works in the ADRWP" function of the program. As you have setup the aforesaid entries, you are ready to enter the list of works. An example of ADRWP entry form is shown in figure-9. Each row in this form in fact represents a "Work" or contract in the ADRWP. The type of works in the list can be one of the items as in table-2.

The general guidelines for defining a piece of work in the ADRWP out of the total development work in the financial year depends on a number of factors which are as follows:

- a) Geographical location of the work, usually a work belongs to a single road.
- b) Type of work, i.e. routine maintenance, periodic maintenance on the same road form separate work or contracts.
- c) Source of funding of the work, i.e. a work can be funded by a single funded source.
- d) Capacity of the contractor in the area to handle a piece of work.

- e) Capacity of the Engineering Setup in the district in terms of equipment, staff to supervise etc.
- f) Small bottleneck work can be combined to another type of work as long as they are funded from a single source of funding.

Table-2: Type of works under ADRWP

		Default Funding
SI. No.	Type of Work	Source
1.	Routine only (RM)	PAF-1
2.	Periodic Maintenance only	PAF-2
3.	Rehabilitation works only	PAF-3
4.	Road Bottleneck works	District Dev. Fund
5.	Structure Bottleneck works	District Dev. Fund
6.	Road Bottleneck (SR) + Structure Bottleneck (ST)	District Dev. Fund
7.	Routine Maintenance + Bottleneck (SR+ST)	PAF-1
8.	Periodic Maintenance + Bottleneck (SR+ST)	PAF-2
9.	Rehabilitation works + Bottleneck (SR+ST)	PAF-3




Figure-9: Tab-1 of List of Works form

There are three tabs in the ADRWP entry forms viz a) Setup Default District, b) Works and c) Expenditure. The last two tabs are shown in figure-10 and figure-11 respectively. Each work in the list are designated by a unique reference number, which are usually a chronological numbers along with one or two digits alphabetic prefix. There is no significance of this unique reference numbers to the QPRS program itself other than it is useful to the users who

can relate the entries in various reports of the program. The QPRS program generates an unique number internally, to refer to each work in the district and even in the country as a whole, to pick and perform various calculative operations on it. The internal numbers generated by QPRS are kept hidden as those are many digits number and do not remain chronological as the user adds and deletes the works list for a particular district.




Figure-10: Work Tab of List of Works form

To add a work in the list, press the command button titled "Add New Work". As you do so, the a new row is added in the form and cursor goes to the first column (i.e. column-r1) of this new row. Define the unique reference number and proceed with other entries in the form. The second entries in the form is the chainage reference which is the location of the work along the road in Km expressed in "From – To" chainage set and separated by comma. When you are entering ADRWP, it can be said that you have already done ADRICS and the road priority number is available. So when you enter the priority number in column-a in the form, QPRS will pick the corresponding road from the RAMPS inventory database and put the road number to column-b. Even if the road priority ranking number is not completed but you have completed the definition of the road network and assigned a set of unique numbers to the network, then can still enter the number in column-b and QPRS will pick the road from inventory database and link it to its database; and then the corresponding road length appears in column-c.

The section length as of column-d is the total length of the work along the road and it is calculated from the entries in column r-2. Now based on the category of work, you once

again enter the size of the work in Km under appropriate columns from e – h. If the work is of routine maintenance category, the total work-days required for the routine maintenance is also calculated considering average condition of road. For any fair condition road (MCI=2.0), total workdays required to maintain 1 Km road is 185. Base on the condition of the road in your situation, calculate the actual workdays required and put the figure under column-f.

The bottlenecks in ADRWP are numbered sequentially with alphanumeric combination starting from A-Z and then when reaches to Z, then it start from A1, A2. up to Z9. The letter 'X' is not allowed to enter for the bottleneck numbers, as that is used to schedule the routine maintenance in form D2 (discussed later). However, as you add a bottlenecks in the ADRWP list, QPRS automatically assigns the next available alphanumeric string for the district, and obviously you can change it to your own choice, as long as the number is alphanumeric starting with a capital letter of the alphabet and the whole set of bottleneck number in the district is unique. The road bottlenecks are entered at the top right table of the screen and the structure bottlenecks are entered at the bottom right table of the screen. Each category of the bottlenecks has its own subcategory (viz new bridge, new culvert and so on) and those sub-categories are entered through the pick lists incorporated with the aforesaid tables. All the bottlenecks must have to specify with a size, which is their dimension along the road and expressed in meter. As you enter or delete the bottleneck under a particular road work, the corresponding list for the bottlenecks are automatically built by QPRS (viz. A, C) and then put them under column I or i.




Figure-11: Work Tab of List of Works form

As the size of each work is defined in form D2, the corresponding cost are calculated based on the unit rate in the database and put it under form D1, which is under the third tab of the

ADRWP entry screen (figure-10). The predefined unit rates are good to have a very approximate estimate of the value of work, however, it is advised to have engineer's estimate of each work and then put them under the form D2.

Each work in the list is assigned against a funding source, and QPRS assigns a default funding source to them depending on the type of work (see table-2). You can always change the funding source for a work, however, it is strongly recommended to assign the funding source very accurately in the beginning of the financial year, otherwise if it is done in the middle of the year, figures in various reports of QPRS will become confusing and they can not be compared with the original Work Plan and the implementation progress. Total amount of money needed for each category of works are summed and displayed under the respective category of works to give you an estimate of how much budget is exploited as you add or delete works in the list. As routine maintenance is always funded from the PAF-1 grant, you can also see form the form D1 the amount of PAF-1 money budgeted in the ADRWP (if they are not shared by other donors). However, accurate funding source-wise summary of the expenditure is done under form D2, which has been discussed in the later section.

5. Schedule of Works and Expenditures in ADRWP

Once the list of works is defined and their cost are entered under form D1 & D2, the next step is in QPRS is to schedule the works on monthly basis over the year. This monthly scheduling or works and expenditures are done using form B2 & B1 respectively. In the QPRS program, there are two tabs under "Schedule of Works & Expenditure" screen, which are titled as "Work" and "Expenditure" and they are used to enter Form-B2 and Form-B1 data respectively. As a matter of fact, during the process of scheduling, the schedule for works in form-B1 is done first and based on which, QPRS calculates the schedule of expenditures over the months.

There are two small tables put on the right side of the screen of "Work" tab, which shows the size and category of the work represented by the row, where you put your cursor. Thus if the work is of Routine Maintenance category, the size of the work (length in Km times work days per Km) is shown in the upper right table of the screen and so on. These two boxes on the right will assist you to decide how do you want to distribute a particular piece of work over the year. If the work is of Periodic Maintenance or Rehabilitation category, split the total length of work over the month such a way that sum of all the split length of works over the year is equal to the total size of the work in the ADRWP. On the other hand, to schedule routine maintenance work in a month, put an 'x' under the respective month and thus all the

'x's entered in a row will represent an equal amount of workdays of routine maintenance, which is total works days for the work as a whole divide by number of months to which the works is scheduled. For example, if the total size of the routine maintenance work is 10 km with total workdays say 1,600 (say @160 WDs per Km) and then the work is scheduled for 8 months, then each 'x' in the corresponding row will denote 1600÷8=200 WDs. Similarly if the bottlenecks are spanned over a number of months, put the corresponding reference number of the bottlenecks against all the months, and QPRS will divide total size of the work equally over each month where the bottleneck reference number appears.




Figure-12: Schedule of Works and Expenditure form

One important thing to mention about the schedule of works for periodic and routine maintenance is that the values in Km represents the completed length of the work in the month. For example, in case of periodic maintenance of a gravel road, let us say total size of the road is 5Km. The work scheduled as follows:

Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb
-	-	2	-	1	2		

It appears from the above table that the amount of work done in the month September is 2Km while no work was done in July and August. Here the fact is that work was done on the road both on July and August, like mobilization of the site, spreading gravel etc. whereas 2Km of the length was finished during the month September. Thus if the total length scheduled in different months is different than the total length of works an error will occur

(when calculate button is pressed) and the QPRS will prompt the user to correct the error. Similarly if any bottleneck is included in the work and not schedule in any month, an error will occur as "Calculate" button is pressed and the user is prompted to correct the error.

The monthly expenditure of the work is calculated as the "Calculate..." button is pressed. The unit cost of work is not this time taken from the predefined unit cost, but from the actual engineer's estimate (or contract bid value) of the work. For instance, if the size of work is 5Km, then from the predefined unit cost, the unit cost of the work might be 8.8x5 million. Whereas if the engineer's estimate for the total work is say 40 million, unit cost of the work will be obviously 8 million (per Km) and the monthly expenditure is calculated accordingly. If we take the example of aforesaid 5Km periodic maintenance, the cost of work calculated in September is 16 million whereas no cost is calculated in July or August. Here the engineer will make his own judgement how he would like to pay to the contractor, after completed length is measured, after mobilization works etc. and s/he can always adjust the monthly expenditure figures which is calculated by QPRS. To calculate a single work, put the cursor on the specific row and then press the "calculate" button. To calculate all the works, check the box "All" (beside the calculate button) and then press "Calculate" button. Remember here that if you have readjusted the monthly expenditure and then press "Calculate" button, QPRS will reset the expenditure schedule from the schedule of work entered in the form-B2.




Figure-13: Schedule of Works and Expenditure form

As you run the calculation and obtain the monthly expenditure of works, the quarterly summary of all works are also calculated and displayed at the footer section of the form. The

quarterly break of the expenditure in percentage is also displayed in a table at the right of "Expenditure" tab, which may help the engineer to adjust the monthly schedule.

6. ADRWP - Budget Summary

After all the works are scheduled and the monthly expenditure schedule is calculated and adjusted, the next step in QPRS is to summarize the expenditure against different funding sources. The summary can be of two different way – viz. activity wise (such as routine maintenance, periodic maintenance and so on and then quarter-wise. Calculation of summary is done under form-D3 of QPRS as shown in figure...There are two tabs in the ADRWP Budget Summary form namely "Quarter-wise Budget Summary" and "Activity-wise Budget Summary". Remember here that unlike Excel or Lotus worksheets, there is no automatic formula inserted with the QPRS which do the summary calculation automatically. Rather, use the "Pick Monthly Exp. of Works" command button to bring the summary expenditure into the form-D3 and save it. That means once you have saved the budget summary figures in form-D3 and after that if you do any change in form D1 figures later, you have to pick the figures from form-D1 again to get the change in the D3 form.




Figure-14: ADRWP Budget Summary (tab-1)

This budget summary form is also used to enter the quarterly budget for operational expenditure in the district. The operational budget is entered under quarter-wise summary tab of the form. As you enter the operational budget, the amount in percentage against each funding source is calculated and displayed in the form so that the engineer gets en estimate about the ceiling of operational expenditure. In the activity-wise summary tab of the form, the

extreme right column is titled as "Budget Ceiling", which displays the budget ceiling for each funding source and enables the engineer to adjust ADRWP to remain within the budget. This budget ceiling figures come from the RAMPS and if you need to do any change in the budget ceiling, you need to do so from the RAMPS module.




Figure-15: ADRWP Budget Summary (tab-2)

7. Actual Works & Expenditure + Planned Next Quarters

Once the list of works is defined and their cost are entered under form D1 & D2, the next step is in QPRS is to schedule the works on monthly basis over the year. This monthly scheduling or works and expenditures are done using form B2 & B1 respectively. In the QPRS program, this function done under the form titled "Actual Works & Expenditure + Planned Next Quarters" (figure-16-19). There are four tabs in the form namely "Work", "Expenditure", "Overall Progress", "Comments". The functions performed in order of operational sequence are as follows:

Table-3: Steps in Entering Monthly Quarterly Progress Data under Form B2/B1

- a. Select Reporting Period (i.e. Quarter)
- b. Pick Monthly Schedule of Works from ADRWP/ Previous Quarter
- c. Enter Actual Works Done (measured quantity) in the Quarter
- d. Schedule Remaining Works over Next Quarter(s) in the FY
- e. Enter Actual Expenditure in the Quarter
- f. Calculate Monthly Expenditure for Next Quarter
- g. Adjust Monthly Expenditure of Works for the Next Quarter

It is a must to follow the sequence of the operations stated in table-3. In fact it is a must to follow the whole sequence of steps of QPRS procedure (table-4) as a whole. If any change in data is done in any of the step in table-4 (or table-3), it is needed to redo the following steps so that the data in all forms in the system remains consistent. For instance, if we take the example in table-3, is the "actual expenditure" under the step-e is edited, then the monthly expenditure of works for the remaining quarter, which is calculated under the step-f of table-3, will remain incorrect. Another possible source of incorrect calculation will occur if any medication in data is done in the previous quarter and the change is not brought to the current quarter by "Pick from Prev. Qrtrs." command. For instance, let us assume that the current quarter is 2nd quarter. All the steps for entering data in form-B2/B1 for the current quarter are done accurately following the table-3. As when everything is done, the user realized that there were some mistakes in entering data in Form B2/B1 the previous quarter, i.e. in quarter-1. Let us assume that the total expenditure in the previous quarter (1st quarter) was 177,506 thousand Shillings. To correct the data in the reporting period of 1st guarter, the user goes back to the quarter-1 and modifies the expenditure to 177,000. Now the user needs to bring the modifications up to the current quarter by entering the command "Pick from Prev. Qrtrs", and follows all the steps in table-3. If it is not done so, amount of "expenditure for first quarter" under the reporting period current quarter (2nd quarter) will be different than that for 1st quarter (reporting period is shown in the blue box in figure-17, next to "Fin Year" box). Refer to the figure-17 and remember that there are four quarter data (i.e. 1st-4th quarter data starting from Jul to Jun) for each reporting quarter.




Figure-16: Actual Works & Expenditure + Planned Next Quarters (Work Tab)

If any modification in data is done for a particular work for a quarter, it is not needed to pick the data of that quarter to the following quarter. For instance refer to figure-16, the amount of work done in September under the work number L02 is 2Km. If the user realize that the correct figure should be 1.5Km, then s/he needs to correct the figure in the reporting period 1st quarter and then follow all the steps of table-3 (i.e. step-c to q) for the work number-L-02. In this case while pressing the "Calc. Monthly Exp. Next Qrtr." command, the user must remember not to check the "All" box next to the command (see figure-17). Because "Calc. Monthly Exp. Next Qrtr." Command will reset the entire expenditure schedule for the remaining quarter(s) (in this example quarter 2-4) under the reporting period for the selected works. Similarly, while picking the data from previous quarter for in case of the aforesaid change in only a few numbers of works, the user should pick the data one by one by putting cursor in the corresponding row of the work and then follow the steps in the table-3 only for the affected works. Note that "Pick from Prev. Qrtrs." command reset the amount of work done and scheduled for all months in form B2, while in case of expenditure (form-B1) it picks the expenditure only for the previous quarter, not for current or following quarter. For example, let us assume that the current reporting period is second quarter. If the 'Pick...." command is entered under this reporting quarter, not only the amount of actual expenditure in the months jul-sep will be reset from the data of reporting period quarter-1, but also the data for the months oct-jun (which is planned works in case of reporting quarter-1) will come from the quarter-1. While you enter data under form B2 and B1, you are allowed to modify the figures for the current and the following quarters. The cells for the current quarter and remaining quarters are displayed in white colour while those for the previous quarter(s) are locked and shown in light blue colour.




Figure-17: Actual Works & Expenditure + Planned Next Quarters (Expenditure Tab)

Under the third tab of the "Actual Works & Expenditure + Planned Next Qrtr(s)" form, a number of useful information about the works in the district are entered (see figure-18). "Mode of Implementation" column describes for a work can be either *Contract* or *Force Account*. There are four columns under the title "Value of work" as follows:

- a) ADRWP
- b) Engineers Estimate
- c) Contract Price
- d) Current Contract Price

The first category of value of work comes from the "ADRWP – List of Works" form (ref. figure-11) and the user is not allowed to change the figure from this form. The ADRWP amount is a rough estimate of the work without detail measurement of the work. Prior the contract is awarded, the Engineer survey and make detail measurement of the work and accordingly gets his estimate of value of work, which refers to the second category of value of work. Contract price refers to the amount which is negotiated with the contractor (note that this can be different than the quoted price by the contractor). As the "Engineers Estimate" or "Contract Price" is entered under respective column, current price becomes the latest value of the work entered in that way. However, even after the contract is awarded, the value of contract may be changed (for instance as because the amount or work is revised or so) and then the user would enter the revise amount under the "Current Contract Price" column. The financial progress of work (column-r) is calculated based on the "Current Contract Price" amount. Apart from the ADRWP amount, the user is allowed to enter all the remaining three category of value of work in the form.

istrict	: Lira				Fin Year: 200	1-02	Quarter: 1st	Jul-Sep	•	<u>Close F</u>	orm	
√ork.	Expenditu	re D	vera	Progress	Comments							
Ref.	Road	Mo				fork ('888 UgX)		Date Cont.	Cont. duration			
Num	Link No	of In	~	ADRWP		-	Current C.Price		(Weeks)	Date	Financial	-
(0)	(a)	(g)	_	(h)	(i)	0)	(k)	(m)	(n)	(0)	(r)	(s)
L01	2201	Cont.	333	41,976	10000000	30,000	0.000	01/08/2001	10.00			
L02	2204	F.Act	•	149,600			149,600				86.9%	10%
L03	2201	Cont.	+	88,000			88,000					
L04	2207		-	132,000			132,000					
L05	2207		-	52,800			52,800					
L06	2207		•	16,088			16,088				7.46%	14%
L07	2204			111,100			111,100				0.54%	5%
L08	2208		₹	7,128		7	7,128				4.21%	20%
L09	2208	- 5		44,000			44,000					
L10	2202		-	15,566			15,566				12.85%	20%
L11	2203		₹	8,606			8,606				23.24%	15%
L12	2206		v	7,942			7,942				12.59%	20%
L13	2205	- 1	-	6,864			6,864				29.14%	25%
L14	2211			11,458			11,458				17.46%	15%

Figure-18: Actual Works & Expenditure + Planned Next Quarters (**Overall Progress Tab**)

The Financial Progress and Physical Progress of work under the overall progress tab (figure-18) are calculated by the "Calc. Monthly Exp. – Next Qrtrs." command. The user is not allowed to change the financial progress figures, as those are calculated based on the actual expenditure in the quarter (form-B1). Whereas the physical progress column is open to edit. In fact the physical progress calculated by QPRS corresponds to the financial value of fully completed length of work. For example if the total size of work is 5 Km and completed length is 3 Km then physical progress calculated by QPRS is 60%. The Engineer can then change the figure as apart from the fully completed length of 3 Km, some more work might have done on the remaining 2 Km. So if the work is measured, the financial equivalent of the measured work will be considered as the physical progress.




Figure-19: Actual Works & Expenditure + Planned Next Quarters (Comments Tab)

The comments tab of the form (see figure-19) is used to enter general and overall comments on progress of the work in a particular quarter. Example of such comments is statement on the slow progress of work etc.

8. QPR – Summary of Expenditure and Next Quarter's Budget

Along with the monthly progress and expenditure of works compiled on quarterly basis, the districts also compiles quarterly summary of all the expenditure against each funding source, using form-D3 (figure-21). This quarterly summary of expenditure is equivalent to the summary report of form-B3. The summary is done two ways viz. quarter-wise summary and activity-wise summary which corresponds to the respective tab in the QPR- Summary Expenditure Form.




Figure-20: Steps in Quarterly Progress Reporting System

The steps in the quarterly progress report summary can be stated as follows:

- a. Enter Funding-Source-wise amount of fund received in the quarter.
- b. Enter amount of operational expenditure done in the quarter.
- c. Enter amount of operational expenditure budget required in the next quarters.
- d. Pick the monthly expenditure from Form B1 & calculate Fund Request for next quarter.
- e. Adjust fund request as per other situations (such as availability of fund) or any other instruction given by the ministry.
- d. Save the summary of Expenditure and Budget in Form-D3




Figure-21: QPR-Summary of Expenditure & Next Quarter's Budget (Quarter-wise Summary Tab)

Similar to other functions in the system, it is very important to follow the steps in the form accurately to get correct result. For instance, the fund request is calculated based on the expenditure planned in the next month and the available balance in the district. If the fund request amount is calculated already and then if somebody change the amount of fund received (which will in turn change the amount of balance with the district) afterwards, the result will be erroneous if the calculation is not done once again. Similarly after picking data from form B1 and then doing all calculations and adjusting figures in form B3, if the user goes back to the form-B1 (for the same or previous quarter) and do some changes there, the calculation in form B3 will become incorrect and there will be inconsistencies between the detail and the summary of expenditures. As you select the reporting quarter in the in the form, the entry cells only under those quarter is open for enter or edit data and all the remaining cells are locked. So if the current reporting quarter is 3rd quarter and you need to

do some change in operational expenditure in second quarter, then you have to go back to the second quarter (through changing the reporting period to **2nd: Oct-Dec** under the reporting quarter pick box) to do so.




Figure-22: QPR-Summary of Expenditure & Next Quarter's Budget (Activity-wise Summary Tab)

The basic principal for calculating the fund request is based on the work plan in the next quarter. Based on the work plan (physical work), QPRS determines the amount of money required to pay to the contractors — which is the financial value of the work planned. Now it may happen that you have some balance of money in the bank from the amount you received so far from the headquarters. You might have some pending payment for the work completed so far and not yet paid (planned to pay in the next quarter). So all these factors are taken into account to determine the "fund request amount" from various funding sources.

Let us take an example. You are reporting the second quarter progress to the headquarters (MoWHC) and requesting for the fund release for 3rd quarter. The financial value of the amount of work done till the 2nd quarter is say (20+35) = 55 million where 20 million equivalent done in the first quarter and 35 million during the second the works under PAF-2 (i.e. periodic maintenance). As this much of work is already completed (as per measurement so far), you are have approved to pay this amount to the contractor (for simplicity, the retention money is not taken into account). Now say so far you have received 10+20 = 30 million from the PAF-2 fund. Out of this 30 million you paid 25 million for the works and expenditure and 5 million balance remain in your bank whereas you need to pay 55-35=25 million. So you need to get another **20** (=25-5) million to pay the work done so far. Instead

of all these complicated way to determine the amount of money need to pay the work done so far is = Value of Work Done so far - Amount received so far = 55 - 35 = 20 million.

Similarly the formula to determine the amount of fund request for the following quarter is as follows:

Value of work - Fund Received

i.e. Value of work done so far + value of work planned in the next quarter – Fund received so far

If we take our previous example, let us say the value of work you planned for the third quarter under PAF-2 fund is say 30 million and we assume you will complete that quantity of work at the end of third quarter. So you expect that at the end of third quarter you will accomplish the work which worth 20+35+30=85 million (20 million in 1st quarter and so on). So at the end of third all together you need 85 million regardless how much you spent (i.e. paid to the contractors) so far. As per aforesaid figures, you received so far 30 million. So you will request for another 55 million (=85-30) for the next quarter to pay the bill.

One important think to mention here that when PAF-1 and PAF-2 fund is released from the Ministry of Finance to the district, it is sent to a single account and no break is mentioned in the release order. Now the district authority needs to break-up the fund and to maintain the account book correctly so that how much fund received, spent and balance against each funding sources can be brought to accurate accountability. As mentioned before, the District Engineer may like alter the amount of fund request different than that determined by the QPRS. The QPRS obviously allows the user to make such changes. Any change in the form D-3 should be stored by "Save Data" command.




Figure-23: QPR-Summary of Expenditure & Next Quarter's Budget (Fund Request Summary Tab)

9. Data Export - Import Operation

The District Engineer sends quarterly progress report data to the Ministry using floppy diskette. The data export operation in QPRS is used to prepare the diskette for the Ministry. The data export interface has been shown in figure-24. By default the exported file is stored under the C:\RAMPS\QPRS\ folder and you need to give a name for the file. As every quarter the headquarters receives data file from all of the 57 districts throughout the country, so it is suggested to name the file with the name of district and quarter suffix so that it is easy for the Ministry to handle the diskettes. Apart from naming the file, the District Engineer should also label and sign the diskette used to send data to the Ministry, although a printed and signed version of the quarterly progress is also sent to the Ministry.




Figure-24: QPRS Data Export Operation

Another purpose of Data Export – Import function is to backup your data. The files which contain data of QPRS system is called QPRS_be.mdb which resides under C:\RAMPS folder. It is strongly suggested that you take a regular backup of this file and store it in a safe place. In some cases the system is operated in different computers, viz the Desktop machine and in a Notebook computer. To exchange the latest data between various computers, this data export-import function can be used. Nevertheless, it is recommended to use a single machine to operate the QPRS, otherwise there is good possibility to mix up the update status of data or loose the updated data. Although the export file is named after the name of reporting quarter, it contains data for all quarters for the selected district and fiscal year. For example if you report 3rd quarter progress for the district Lira, name the export file as Lira_Qrtr3.MDB, although the file contains all the three quarter starting from quarter-1.

The reason for including all quarter data is if you have made any change in the previous quarter data, you have corrected it only at your machine – also the other machine where your data are copied (e.g. the headquarters machine), they also need to get the correct date. If it is not also corrected, then not only the data of the district and headquarters are different, but also in the headquarters, the data among various quarters are also become inconsistent.

Another important thing to remember that when the headquarters imports data into their server using RAMPS-HQ module, they pick only one district data from the diskette. So if your diskette contains multiple district data (for instant you have incorporated Lira district data for your practice while your own district is Gulu), the headquarter module will pick the first district data it founds in your diskette (which may be Lira) and will drop your district. To avoid such situation, remember to tick only your district name in the data export form and do not tick any other district! (see figure-24).

10. Lookup Tables of RAMPS in QPRS

There are a number of lookup tables used by QPRS programme and all of them except the Unit Table come from the primary modules of RAMPS. That means, if you do any change in the lookup table put under RAMPS primary module, the change automatically comes to the QPRS module. Similarly if you make any change in any of the lookup table from QPRS module (for example you change spelling of a district), the change will automatically goes to the RAMPS module. The exception here is the Unit Cost table where a separate set of Unit cost is maintained in RAMPS and QPRS modules.




Figure-25: Lookup tables of RAMPS in QPRS module (Worklist Tab)

The lookup table tabs available in QPRS are as follows:

- a) Worklist
- b) Unit Cost
- c) Funding Source
- d) District Table




Figure-26: Lookup tables of RAMPS in QPRS module (Unit Cost Tab)




Figure-27: Lookup tables of RAMPS in QPRS module (Funding Source Tab)




Figure-28: Lookup tables of RAMPS in QPRS module (District Table Tab)

11. Reports in QPRS

There are 15 reports built in the current version of QPRS (figure-29). The first five reports are in fact the reports of RAMPS which put under QPRS to make them readily available



Figure-29: Reports in QPRS

there. The remaining 10 reports are specific to the QPRS and they are self explanatory from their titles. A sample set of reports are also included in the Appendix-C. The data in the reports can be filtered out using the filter tables with the report form (figure-30). There are six

set of filter tables provided with the filter page of QPRS, out of which the District Filter and the Quarter filter are commonly used. The Financial Year name in the Report form come from the default financial year settings, which can be set at the "List of Works ..." form (figure-9).





Figure-29: Filtering tables of QPRS Reports

APPENDICES

Structure Diagram of QPR Database



Trouble Shooting Appendix-B


1. Installation Related Problems

Installation of QPRS is a part of installation of other components in the RAMPS Applications. So it is required that other components (like MS Access Runtime) of the Application are installed before in your machine. The installation program is activated as when the installation CD is inserted into the drive. Now the installation program will not be activated if the "auto insert notification" feature of the particular CD drive is disabled in your machine. Activation of the "auto insert notification" feature varies from one Operating System to other. Instead, if not activated automatically, the best method is to start the program by clicking BatchSetup.exe file from Windows Explorer. The BatchSetup.exe is available under the root directory of the installation CD.

The BatchSetup.exe is again developed in Visual Basic and it requires some visual basic runtime Dynamic Link Library (DLL) files. Those DLL files come with the Windows Operating System (except that customized installation of the OS or with the old OS) by default. However, if BatchSetup.exe does not find the required VB runtime DLLs, it will not work. The installation CD of RAMPS Application contains the VB runtime files under the folder \VBRun and running the file \VBRun\VBRun60sp5.exe will install the runtime DLL files required to run installation programs in your machine.

2. The Reports does not fit in the page


The reports of QPRS program have been designed for A4 size paper (8.27"x11.69") which is the standard paper available in the country. However, the default paper size in most of the printer is set as Letter (8.5"x11") size, which is the standard size in the US, but shorter than A4. So change the default paper size to A4 to make it same as the paper what you use. The paper size can be changed from the property Settings of the Printer.



Trouble Shooting Appendix-B

3. Date Settings

The British system for Date is followed in the RAMPS application where date is followed by the month. In contrary, under the US system for date, month is followed by the date. So if the date setting in your machine is the US system, any date entered as 05/03/2001 will be regarded as May 3, 2001 whereas you meant the 5th of March, 2001. So it is essential that you check and change the date setting of your machine. The date setting is found under the "Region" settings in the Control Panel.



4. Trouble Shooting Startup Video

The RAMPS applications play a startup Audio Video Interleaved (AVI) format video clip, which is built in the RAMPS/ QPRS Interface using a Microsoft Media Player (MPlayer version 2.0) control. Now to run the interface, it is needed that the Media Player control has been installed in your machine correctly during the installation of the Operating System. The current version of Windows Media Player (WMP) is 9.0 which requires Windows OS 98 SE (Second Edition) or higher, 64 MB RAM (128 recommended), 233 MHz CPU speed (500 MHz recommended) and so on. Most of the machines presently available in the market have much higher configuration than above; however many machines in the district office may not have the minimum requirement for WMP 9.0. As such, to ensure that the RAMPS applications would run properly in all machines, an old version of media control has been used. Because, whatever version of OS, Office Suit or WPM installed in your machine, the AVI interface for MPlayer 2.0 is built in there by default (Microsoft Media Player control is different than Windows Media Player). The problem here is that when some third party

Trouble Shooting Appendix-B

multimedia program is installed, they may corrupt the old version of MPlayer control. In such case the startup video may not run and may prohibit activation of the main Switchboard of RAMPS application. Solution of such problem depends on the source and nature of the problem, which may vary in numbers. For example, one solution could be installation of Windows Media Player version 9.0 or version 7.1, which may, however, cause instability in other third party program. So the best option is to deactivate the Startup Video Clip. The enable or disable property for startup video clip has been built in the RampsLUT.mdb file and this can be accessed using a Visual Basic Program called RemoveMovie.exe, which has been supplied with the RAMPS installation CD. The RemoveMovie.exe again needs MS Data Access Component if it is not already installed in your machine. The setup files for MS Data Access Component version 2.5 have been provided under the MSDAC25 folder of the RAMPS installation CD.

Reports of Q P R S

Page 1 of 1 08/03/2003

Second Quarter

OPR - DISTRICT ROAD WORKS SHOWING OVERALL PROGRESS

Distr	District: Lira							FY: 2002-03	02-03											
Work	Work Reference			Road	Length		Type	Mode of	>	Value of Work ('000 UgX)	k ('000 UgX		Bid	Date Co	Contract Co	Comple-	Time	Amount	Progress of Work	of Work
Num	Chainage	Road	Road Name	Length	of Work	Funding Source	Jo	Imple-	Work Plan	Engineers	Contract	Current Ra	Rate Co	Contract Duration		tion	lapsed P	Elapsed Paid To-date	Physical Financial	Financial
	(From-To)	Code		(Km)	(Km)		Work	mentation	Estimate	Estimate	Price	Cont. (9	(%) Aw	Awarded (Weeks)		Date (9	(% of n)	(XgU 000)	(%)	(%)
(r1)	(r2)	(a)	(q)	(c)	(p)	(e)	(f)	(g)	(h)	(i)	(j)	(k) ((I)	(m)	(u)	(0)	(d)	(b)	(r)	(s)
L01	0-10.5	2229	Kangai - Kwera	10.50		10.5 PAF-3	RH		277,200			277,200			0.00			277,200	100 %	100.0%
L02	0-4	2223	Corner Odyak - Muntu	10.00) 4	District Dev Fun	RH		105,600			105,600			0.00			105,600	100 %	100.0%
L03	0-4	2215	Odokomit - Apac Border	00.9) 4	PAF-3	RH		105,600			105,600			0.00			105,600	100 %	100.0%
L04	0-2.7	2215	Odokomit - Apac Border	00.9	2.7	PAF-1	RM		1,424			1,424			0.00			970	20 %	43.6%
T05	0-20	2228		20.00		20 PAF-2	PM		176,000			176,000			0.00			176,000	100 %	100.0%
90T	0-5	2219	Chwagere - Kwera Port	15.00) 5	District Dev Fun	PM		44,000			44,000			0.00			44,000	100 %	100.0%
L07	0-15	2219	Chwagere - Kwera Port	15.00) 15	PAF-1	RM		606'L			606'1			0.00			3,960	43.2 %	50.1%
R07	0-4	2224	Dokolo - Soroti Border	4.00) 4	Other	RM		2,109			2,109			0.00			1,055	41.9 %	20.0%
60T	0-4.1	2203	Lira - Boroboro - Soroti Road	8.10	4.1	PAF-1	RM		2,162			2,162			0.00			1,080	46.1 %	20.0%
L10	0-4	2203	Lira - Boroboro - Soroti Road	8.10		0 Donor - DANIDA	SR		7,000			7,000			0.00				% 0	%0.0
L11	0-10	2204	Aloi - Dokolo	44.00		0 Donor - DANIDA	SR		7,000			7,000			0.00				% 0	%0.0
L12	0-34	2204	Aloi - Dokolo	44.00		34 PAF-1	RM		17,927			17,927			0.00			8,965	47.7 %	20.0%
L12	0-12.5	2205	Abako - Katakwi Border	17.55	5 12.55	PAF-1	RM		6,617			6,617)	0.00			3,305	43.1 %	46.6%
L13	0-5	2205	Abako - Katakwi Border	17.55		0 Donor - DANIDA SR	SR		8,000			8,000			0.00				% 0	%0.0
L14	0-2	2211	Namasale- Awelo	33.00		0 Donor - DANIDA	SR		2,000			2,000			0.00				% 0	%0.0
L15	0-31	2211	Namasale- Awelo	33.00		31 PAF-1	RM		16,345			16,345			0.00			8,165	47.1 %	20.0%
L16	0-2	2208	Acanpii - Katakwi Border	18.00	0 (Donor - DANIDA	SR		2,000			2,000	-		00:00				% 0	%0.0
L17	0-16	2208	Acanpii - Katakwi Border	18.00		16 PAF-1	RM		8,436			8,436	_		0.00			4,220	42.2 %	20.0%
L18	0-20.7	2201	Ngetta - Apala	20.70		20.7 District Dev Fun	RM		10,914			10,914	_		0.00			5,460	31.6 %	20.0%
									808,242			808,242						745,230	91.6%	92.2%

Signed (CAO)

Date:



2,591 2,591 2,591 2,591 2,591

2

2,591 2,591 2,591 2,591

2,591

Fotal Works RM: WD

∞ ∞

<u>~</u> 8

3 2

PM: Km RH: Km

Planned Per Month

7,773

5,182

5,182

7,773 2.0 2.5

Fotal Works RM: WD

PM: Km RH: Km

Planned Per Quarter

16.0 20.0

Page 1 of 1 08/03/2003

ADRWP Form-D2

ADRWP - WORKS IMPLEMENTATION SCHEDULE

FY: 2002-03

District: Lira

																							□ I +
		<u> </u>	(v)				20			278	74	9/			629	232			573		296	383	2 501
		MAY	(n)				20			278	74	9/			629	232			573		296	383	2 591
edule		APR	(t)				20			278	74	92			629	232			573		296	383	2 591
n Sch		MAR	(s)				20			278	74	92	∢	В	629	232	ပ	۵	573	ш	296	383	2 591
entatio		2	(r)				20			278	74	92	<	В	629	232	ပ	Δ	573	ш	296	383	2 591
nplem		NAN	(b)																				
orks Ir		DEC	(d)					2															
thly W		NOV NOV	(0)	4	2	2	20	2	က	278	74	9/			629	232			573		296	383	2 591
Planned Monthly Works Implementation Schedule		OCT	(n)	4	2	2	20	2	2	278	74	9/			629	232			573		296	383	2 591
Planne		SEP	(m)	2.5			20	2		278	74	9/			629	232			573		596	383	2 591
\lfloor		AUG	(1)				20			278	74	9/			629	232			573		296	383	2 501
		귋	(k)				20			278	74	92			629	232			573		296	383	2 591
	Map Loc	Ref. for SR/ST	(i)																				
			(i)																				Total Works RM: WD
	Road	Bt'l Neck Bt'l Neck (SR)	(h)										∢	В			ပ	۵		ш			Total W
tivities		litation (Km)	(g)	10.50	4.00	4.00																	18.50
s and Ac	Periodic	Maint. (Km)	(f)					20.00	5.00														25.00
Planned Intervention Descriptions and Activities	Routine	Maint. (WD)	(e)				499.5			2775	740	758.5			6290	2321.8			5735		2960	3829.5	25,909
ntion Des	Section	Length (Km)	(p)	10.50	4.00	4.00	2.70	20.00	5.00	15.00	4.00	4.10	4.00	10.00	34.00	12.50	5.00	2.00	31.00	2.00	16.00	20.70	
Interver	Road	Length (Km)	(c)	10.50	10.00	00.9	00.9	20.00	15.00	15.00	4.00	8.10	8.10	44.00	44.00	17.55	17.55	33.00	33.00	18.00	18.00	20.70	
lanned		Road Code	(q)	2229	2223	2215	2215	2228	2219	2219	2224	2203	2203	2204	2204	2205	2205	2211	2211	2208	2208	2201	
	District	Priority Rank	(a)	-	2	8	8	4	2	2	9	7	7	80	80	6	6	10	10	11	11	12	
	Work Reference	Chainage (From-To)	(r2)	0-10.5	0-4	0-4	0-2.7	0-20	0-5	0-15	0-4	0-4.1	0-4	0-10	0-34	0-12.5	0-5	0-2	0-31	0-2	0-16	0-20.7	
	Work	Num.	(r1)	L01	L02	F03	L04	L05	907	L07	F08	607	120	7	L12	L12	L13	L14	L15	L16	L17	L18	

ist of Bottlenecks in the ADRWP	
ist of Bottlenecks in the ADRW	Δ
ist of Bottlenecks in the ADRV	
ist of Bottlenecks in the ADF	
ist of Bottlenecks in the AD	\sim
ist of Bottlenecks in the A	=
ist of Bottlenecks in the A	
ist of Bottlenecks in the	
ist of Bottlenecks in the	
ist of Bottlenecks in th	
ist of Bottlenecks in	
ist of Bottlenecks ir	-
ist of Bottlenecks i	_
ist of Bottleneck	
ist of Bottleneck	
ist of Bottlenec	
ist of Bottlene	
ist of Bottlene	=
ist of Bottler	
ist of Bottle	
ist of Bott	Φ
ist of Bot	
ist of Bo	
ist of	'n
ist of	m
ist o	_
ist	
<u>s</u>	0
	_
	Š

		Size	Cost
Code	Code Bottleneck Tyne	(Im)	('000 UaX)
٧	Embankment Filling	4,000.0	7,000
В	Embankment Filling	0,000,0	7,000
С	Embankment Filling	5,000.0	8,000
D	Embankment Filling	2,000.0	2,000
Е	Embankment Filling	2,000.0	2,000

2,000.0 2,000
2,000.0 2,000
5,000.0 8,000
0,000,0
4,000.0 7,000

Date:

Date:

, o	000
_	
age	00/00
ď	•

ADRWP Form-D1

ADRWP - EXPENDITURE SCHEDULE

FY: 2002-03

District: Lira

2,109 16,345 8,436 10,914 808,242 44,000 7,909 7,000 7,000 8,000 2,000 2,000 872,242 277,200 105,600 105,600 176,000 17,927 6,617 64,000 Budget Total Annual 3 1,793 7,384 1,634 1,091 142 211 662 844 791 Ŋ 3 7,384 22,152 16,000 38,152 1,793 662 1,634 844 1,091 142 216 MAY 791 211 Ξ Planned Monthly Expenditure Schedule ('000 UGX) 7,384 1,634 142 216 1,793 844 211 662 1,091 791 APR (s) 1,634 20,384 3,500 3,500 1,793 662 4,000 1,000 844 1,091 MAR 142 216 1,000 791 211 Ξ 20,384 1,634 40,768 16,000 56,768 3,500 3,500 1,793 4,000 1,000 844 142 662 1,000 1,091 791 盟 **b** JAN (d) 44,000 44,000 0 7,384 117,384 280,184 288,984 629,168 613,168 44,000 105,600 52,800 52,800 26,400 216 1,793 1,634 844 16,000 1,091 791 211 662 Š <u>u</u> 105,600 1,091 52,800 52,800 44,000 17,600 142 216 844 1,793 662 1,634 211 791 OCT Ξ 99,000 44,000 1,793 1,634 1,091 216 844 142 791 211 662 SEP \equiv 132,152 148,152 1,793 1,634 844 1,091 662 16,000 142 216 791 211 AUG 3 7,384 1,793 662 1,634 844 1,091 142 211 791 Ŋ 9 Struct. Bt'l Neck \equiv Bt'l Neck 7,000 7,000 8,000 2,000 2,000 26,000 Road Cost (F) Planned Intervention Descriptions and Costs ('000 UGX) 105,600 105,600 488,400 277,200 Routine Periodic Rehabi-Maint. Maint. litation Cost Cost Cost (g) 220,000 176,000 44,000 =otal Monthly Expenditure of Works Implementation: 'otal Quarterly Expenditure of Works Implementation 73,842 2,109 8,436 7,909 2,162 10,914 1,424 16,345 17,927 6,617 otal District Fiscal Year Expenditure by Quarter (e) otal Quarterly Operational Expenditure: Section Length (Km) 4.00 4.00 2.70 20.00 5.00 15.00 4.00 4.10 4.00 10.00 34.00 12.50 2.00 31.00 2.00 16.00 20.70 10.50 5.00 **©** Road Length (Km) 20.70 44.00 10.50 8.10 44.00 33.00 18.00 10.00 00.9 00.9 20.00 15.00 15.00 4.00 8.10 17.55 17.55 33.00 18.00 (C) Total Intervention Costs: Road Code 2229 2223 2215 2215 2228 2219 2219 2224 2203 2203 2204 2204 2205 2205 2208 2208 2201 2211 2211 **Q** District Priority Rank 9 10 Ξ 7 12 <u>a</u> က 2 9 တ တ $^{\circ}$ က 4 2 ω ω Work Ref. Num L13 L15 L16 **L**0 L02 L03 L04 L05 P00 L07 L08 F03 L11 L12 L12 L17 L10 L14 0

Signed (CAO)

ADRWP - Budget Summary (Form-D3)

PLANNED SOURCE OF FUNDING

Form-D3.a Figures in '000 UGX

Total Annual Works + Operational Operational Expenses Sub-Total (All Works) Road Structure Bottleneck (SR) **Expenditure for Works** Rehabilitation (RH) Periodic Maint. (PM) Routine Maint. (RM) **Funding Source**

PAF-1	60,818				60,818	10,000	70,818
PAF-2		176,000			176,000	9,000	182,000
PAF-3			382,800		382,800	40,000	422,800
District Dev Fund	10,914	44,000	105,600		160,514	4,000	164,514
Donor - DANIDA				26,000	26,000	4,000	30,000
Other	2,109				2,109		2,109
Total:	73,841	220,000	488,400	26,000	808,241	64,000	872,241

Date:

Signed (CAO)

Signed (DLGE)



ADRWP - Budget Summary (Form-D3)

QUARTERLY BUDGET SUMMARY

Page 1 of 2 08/03/2003

Form-D3.b

Figures in '000 UGX

	100.0 %			92.6 %			89.1 %			17.0 %		Cummul. Qrtr'ly Percentage:
	872,242			834,089			777,321			148,152		Cummulative Qrtr'ly Total:
38,152			56,768			629,168			148,152			Fotal for Quarter:
		633			422			422			633	Other
1,000	1,000		27,000	1,000	26,000	1,000	1,000		1,000	1,000		Donor - DANIDA
4,274	1,000	3,274	3,183	1,000	2,183	152,783	1,000	151,783	4,274	1,000	3,274	District Dev Fund
10,000	10,000		10,000	10,000		326,800	10,000	316,800	76,000	10,000	66,000	PAF-3
1,500	1,500		1,500	1,500		133,500	1,500	132,000	45,500	1,500	44,000	PAF-2
20,746	2,500	18,246	14,664	2,500	12,164	14,664	2,500	12,164	20,746	2,500	18,246	PAF-1
Total	Operational	Works	Total	Operational	Works	Total	Operational	Works	Total	Operational	Works	Funding Source
	4th Quarter			3rd Quarter			2st Quarter			1st Quarter		
I Igaics III ood ook	i igales											

Date:

Signed (CAO)

Signed (DLGE)



Page 1 of 2 08/03/2003

QPR - WORKS IMPLEMENTATION SCHEDULE

FY: 2002-03

Second Quarter OPR Form-R2

Distri	District: Lira																						QP _F	QPR Form-B2	B2
	^	Vork Re	Work Reference			IN	INTERVENTION	NOIL		Planned	Planned Vs Actual Work	al Work			Ac	tual W	Actual Works Done To-Date	one Tc	-Date	& Plan	ned Ne	& Planned Next Quarters	rters		
Work	Work Reference District	District		Road (Section	-								1st	1st Quarter	ı	2nd (2nd Quarter	L	3rd Q	3rd Quarter		4th Q	4th Quarter	
Num	Chainage	Priority Pople	Road	٦	Length	Type	_			Actual	Planned		Differn.	⋖⊢	Actual	į	⊢≽	⊢	_	Pla	nned .	:	Plar	ᆽ	
	(From-To)	Kank	Code	(KM)	(MM)		(MM)	NK/VI Kei	This Qrtr	This Qrtr	To-Date	To-Date	To-Date	JUL	AUG	SEP	ОСТ	NON	DEC	JAN	HB	MAR	APR	MAY	NOS
(r1)	(r2)	(a)	(q)	(c)	(p)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	((m)	(n)	(0)	(d)	(b)	(r)	(s)	(t)	(n)	(×)	(w)	(×)
L01	0-10.5	_	2229	10.50	10.50	RH	10.5		8.0	8.0	10.5	10.5				2.5	4	4							
L02	0-4	2	2223	10.00	4.00	RH	4		4.0	4.0	4.0	4.0					2	2							
L03	0-4	8	2215	00.9	4.00	RH	4		4.0	4.0	4.0	4.0					2	2							
L04	0-2.7	က	2215	00.9	2.70	RM	2.7		100	100	250	250		20	20	20	20	20			20	20	20	20	20
L05	0-50	4	2228	20.00	20.00	PM	20		15.0	15.0	20.0	20.0				2	2	2	2						
90T	0-5	2	2219	15.00	2.00	PM	2		5.0	5.0	5.0	5.0					2	8							
L07	0-15	2	2219	15.00	15.00	RM	15		621	009	1,221	1,200	-21	200	200	200	300	300			315	315	315	315	315
F08	0-4	9	2224	4.00	4.00	RM	4		151	100	361	310	-51	20	20	20	20	20			98	98	98	98	98
60T	0-4.1	7	2203	8.10	4.10	RM	4.1		157	140	367	350	-17	20	20	20	20	20			82	82	82	82	82
L10	0-4	7	2203	8.10	4.00	SR	0	4													4	4			
L11	0-10	8	2204	44.00	10.00	SR	0	В													В	В			
L12	0-34	8	2204	44.00	34.00	RM	34		1,283	1,200	3,083	3,000	-83	009	009	009	009	009			658	928 (928 (9 859	658
L12	0-12.5	6	2205	17.55	12.50	RM	12.55		492	400	1,092	1,000	-92	200	200	200	200	200			264	264	264	264	264
L13	0-2	6	2205	17.55	5.00	SR	0	ပ													ပ	ပ			
L14	0-2	10	2211	33.00	2.00	SR	0	D													٥	۵			
L15	0-31	10	2211	33.00	31.00	RM	31		1,210	1,200	2,710	2,700	-10	200	200	200	009	009			209	09) 209) 209	209
L16	0-2	11	2208	18.00	2.00	SR	0	ш													ш	ш			
L17	0-16	11	2208	18.00	16.00	RM	16		099	009	1,310	1,250	09-	200	250	200	300	300			342	342	342	342	342
L18	0-20.7	12	2201	20.70	20.70	RM	20.7		920	009	1,530	1,210	-320	200	210	200	300	300			524	524	524	524	524
ADRWP	WP RM: WD	L	25,909					RM: WD	5,594	4,940	11,924	11,270	-654	2,090	2,150	2,090	2,470	2,470		2,928	2,928	2,928	2,928 2	2,928 2	2,928
Total	l PM: Km	Km	25.0					PM: Km	20.0	20.0	25.0	25.0				2.0	7.0	8.0	2.0						
	RH: Km	Æ	18.5				_	RH: Km	16.0	16.0	18.5	18.5				2.5	8.0	8.0					Н		

		Size	Cost
ode	ode Bottleneck Type	(Im)	('000 UgX)
٧	Embankment Filling	4,000.0	2,000
В	Embankment Filling	0.000,0	2,000
၁	Embankment Filling	5,000.0	8,000
D	Embankment Filling	2,000.0	2,000
E	Embankment Filling	2,000.0	2,000

List of Bottlenecks in the ADRWP

Comments:

Total Works	RM: WD	6,330	4,940	8,784	8,784
Per Quarter	PM: Km	5.0	20.0		
	RH: Km	2.5	16.0		

Date:

16,000

Total Operational Expenditure Per Quarter: Total District FY Expenditure Per Quarter:

148,098 16,000

25,033

42,689

Page 1 of 1 08/03/2003

OPR - EXPENDITURE SCHEDULE

FY: 2002-03

Second Quarter

District:	xt:Lira									 F	FY : 2002-03	m								Sec	Second Quarter QPR Form-B1	arter n-B1
Wor	Work Ref.	N	INTERVENTION	NOL		Planne	d Vs Actu	Planned Vs Actual Expenditure	diture				Actual	Expend	iture To	o-Date	Expenditure To-Date & Planned Next Quarters	ed Next	Quarte	ers		
Work		Tvne	l pnoth	ADRWP	ī		i		3		1st Quarter		Actual	2nd	2nd Quarter		3rd G	3rd Quarter		4th (4th Quarter	
Num	Code			Cost	Planned This Qrtr	Actual This Qrtr	Planned To-Date	Actual To-Date	Differn. To-Date	Outstand. Payment	JUL	AUG	SEP	OCT O	NOV	DEC	JAN		MAR	APR	MAY	NOC
(0)	(a)	(q)	(c)	(p)	(e)	(f)	(g)	(h)	(i)	(i)	(k)	(1)	(m)	(n)	(0)	(d)	(b)	(r)	(s)	(t)	(n)	(v)
L01	2229	RH	10.5	277,200	211,200	211,200	277,200	277,200					900'99	105,600	105,600							
L02	2223	RH	4	105,600	105,600	105,600	105,600	105,600						52,800	52,800							
L03	2215	RH	4	105,600	105,600	105,600	105,600	105,600						52,800	52,800							
L04	2215	RM	2.7	1,424	285	248	657	979	-37		124	124	124	124	124			142	142	142	142	142
L05	2228	PM	20	176,000	132,000	132,000	176,000	176,000					44,000	900,99	900'99							
P00	2219	PM	2	44,000	44,000	44,000	44,000	44,000						44,000								
L07	2219	RM	15	2,909	1,771	1,584	4,147	3,960	-187		792	792	792	792	792			868	868	868	868	868
F08	2224	RM	4	2,109	432	422	1,065	1,055	-10		211	211	211	211	211			245	245	245	245	245
F00	2203	RM	4.1	2,162	447	432	1,095	1,080	-15		216	216	216	216	216			233	233	233	233	233
L10	2203	SR	0	7,000														3,500	3,500			
L11	2204	SR	0	7,000														3,500	3,500			
L12	2204	RM	34	17,927	3,656	3,586	9,035	8,965	-70		1,793	1,793	1,793	1,793	1,793			1,875	1,875	1,875	1,875	1,875
L12	2205	RM	12.55	6,617	1,402	1,322	3,385	3,305	-80		199	199	199	199	199			753	753	753	753	753
L13	2205	SR	0	8,000														4,000	4,000			
L14	2211	SR	0	2,000														1,000	1,000			
L15	2211	RM	31	16,345	3,449	3,266	8,348	8,165	-183		1,633	1,633	1,633	1,633	1,633			1,730	1,730	1,730	1,730	1,730
L16	2208	SR	0	2,000														1,000	1,000			
L17	2208	RM	16	8,436	1,881	1,688	4,413	4,220	-193		844	844	844	844	844			975	975	975	975	975
L18	2201	RM	20.7	10,914	2,622	2,184	5,898	5,460	-438		1,092	1,092	1,092	1,092	1,092		┨	1,493	1,493	1,493	1,493	1,493
Expen	Expenditure of Works :	f Works		808,242	614,343	613,132	746,441	745,230	-1,211		7,366	7,366	117,366	328,566	284,566			21,344	21,344	8,344	8,344	8,344
						Total Exp	enditure	Total Expenditure of Works Per Quarter	Per Qua	rter :		132,098					4	42,689		5	25,033	

Signed (CAO)

Date:

Page 1 of 4 08/03/2003 First Quarter

2PR - SUMMARY OF ACTUAL EXPENDITURE & FUND REQUEST (Form-B3)

FY: 2002-03

Figures in '000 UGX

															1.84	igales III ese ese	
:			Actual Ex	Actual ExpenditureThis Quarter	his Quarte	j.		Quarte	Quarter-wise Total Actual Expenditure	Actual Expo	enditure	Fun	Fund Spent To-Date	-Date	Planned	% Progress	gress
Funding Source	Routine	Periodic	Periodic Rehabili-	Road	Struct.	Sub-Total	Opera-	1st Ortr	2nd Ortr	3rd Ortr	4th Ortr	Works	Opera-	Total	Annual	To-Date	ate
	Maint.	Maint.	tation	Btl'Neck	Btl'Neck	(Works)	tional	5		5	; ;	2	tional		Budget	Planned	Actual
PAF-1	18,189					18,189	2,500	20,689		1		18,189	2,500	20,689	70,818	34.1%	29.9%
PAF-2		44,000				44,000	1,500	45,500				44,000	1,500	45,500	182,000	25.9%	25.0%
PAF-3			000'99			000'99	10,000	76,000				000'99	10,000	76,000	422,800	19.9%	17.2%
District Dev Fund	3,276					3,276	1,000	4,276				3,276	1,000	4,276	164,514	2.7%	2.0%
Donor - DANIDA							1,000	1,000	,				1,000	1,000	30,000	3.8%	%0:0
Other	633					633		633	,			633	1	633	2,109	30.0%	30.0%
Sub-total PAF Fund:	18,189	44,000	000'99			128,189	14,000	142,189		•		128,189	14,000	142,189	675,618	23.0%	20.7%
Total:	22,098	44,000	000'99			132,098	16,000	148,098	•	•	•	132,098	16,000	148,098	872,242	18.3%	16.3%
Cummulative Expenditures in the Quarters (in Amount)	litures in th	he Quarter	s (in Amou	nt)				148,098	•	•	•						
Cummulative Expenditures in the Quarters (in %)	litures in th	ne Quarters	(in %)					17.0%									

:	Ь	UND REC	FUND REQUEST FOR DIFFERENT ACTIVITIE	OR DIFFE	RENT A		S	Total Fund	Value of	Fund	Fund Spent To-Date	nt To-Date			Value		
Funding Source	Routine Maint.	Periodic Maint.	Periodic Rehabili- Maint. tation	Road Btl'Neck	Struct. Sub-Total Btl'Neck (Works)	Struct. Sub-Total Btl'Neck (Works)	Opera- tional	Request (Wrk.+Opr)	Work To-Date	Received To-Date	Works	Opera'tnI	Unspent Balance	Commit- ments	of Work Next Ortr.	Payment Next Ortr.	Fund Required
(a)	(q)	(c)	(p)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(1)	(m)	(u _{**})	(I-j=0)	(d)	$(d_* = 0+p)$	(r* =q-n)
PAF-1	11,094					11,094		11,094	15,704	20,000	18,189	2,500	689-	-2,486	12,890	10,404	11,093
PAF-2		127,500				127,500		127,500	44,000	50,000	44,000	1,500	4,500	1	132,000	132,000	127,500
PAF-3			322,800			322,800		322,800	000'99	70,000	000'99	10,000	000'9-		316,800	316,800	322,800
District Dev Fund	4,247	42,857	102,856			149,960		149,960	1,739	5,000	3,276	1,000	724	-1,538	152,222	150,684	149,960
Donor - DANIDA												1,000	-1,000	1			1,000
Other	1,030					1,030		1,030	299		633		-633	-35	432	397	1,030
Sub-total PAF Fund:	11,094	127,500	322,800			461,394		461,394	125,704	140,000	128,189	14,000	-2,189	-2,486	461,690	459,204	461,393
Total:	16,370	170,357	425,656			612,384		612,384	128,041	145,000	132,098	16,000	-3,098	-4,058	614,343	610,286	613,384

(DLGE)

(CAO)



* Only work related amounts; ** Unspent Balance=(k-l-m); This should be confirmed with Bank Statement




PLAN Vs ACTUAL WORK DONE UNDER ROUTINE MAINT.

Page 1 of 1 08/03/2003

District: Lira FY: 2002-03

Second Quarter







Plan Vs Actual Expenditure under PAF 1 & 2

Page 1 of 1 08/03/2003

District: Lira

FY: 2002-03





Plan Vs Actual Expenditure under PAF 3



District: Lira FY: 2002-03

Second Quarter

